

LOCATION OF WORK:

FAI 74
RURAL
INTERSTATE
MCLEAN COUNTY
STA. 737+00 TO STA. 1111+00
E OF US 51 TO CH 36 AT DOWNS

FUNDING BREAKOUT:
CONSTRUCTION TYPE CODE:

90% FEDERAL / 10% STATE
0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
50105220	PIPE CULVERT REMOVAL	FOOT	16.0
50300225	CONCRETE STRUCTURES	CU YD	16.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,129.0
54002010	EXPANSION BOLTS 1/2 INCH	EACH	40.0
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1.0
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	5.0
54248510	CONCRETE COLLAR	CU YD	7.2
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	16.0
550B0020	STORM SEWERS, CLASS B, TYPE 1 6"	FOOT	85.0
550B0070	STORM SEWERS, CLASS B, TYPE 1 15"	FOOT	103.0
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	16.0
550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FOOT	14.0
55100200	STORM SEWER REMOVAL 6"	FOOT	75.0
55100500	STORM SEWER REMOVAL 12"	FOOT	16.0
55100700	STORM SEWER REMOVAL 15"	FOOT	115.0
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1.0
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	875.0
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3.0
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	2.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	3.0

* DENOTES SPECIALTY ITEM

FILE NAME *	USER NAME * hogenbj	DESIGNED - BJH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pvc\work\pvidot\hogenbj\d0158340\0570550-sh1-S00.dgn	DRAWN - BJH 10/12/2010	REVISED -						74	(57-20(1)),21,22RS-3	MCLEAN	150	10
PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -			CONTRACT NO. 70550			ILLINOIS FED. AID PROJECT				
PLOT DATE = 10/28/2010	DATE -	REVISED -			SCALE: _____	SHEET NO. 4 OF 7 SHEETS	STA. _____ TO STA. _____					