

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI-39 MCLEAN CO. STATION 41+92.0 TO 198+61.67 MULTILANE 100% STATE <u>0004</u>	FAI-39 MCLEAN CO. STATION 198+61.67 TO 557+87.88 RURAL-MULTILANE 100% STATE <u>0004</u>
--	--

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY		
44200549	CLASS A PATCHES, TYPE I, 10 INCH	SQ YD	4.0		4.0
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	143.0		143.0
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	96.0		96.0
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	313.0		313.0
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	110.0	86.0	24.0
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	20.0		20.0
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	80.0	40.0	40.0
44201299	DOWEL BARS 1 1/2"	EACH	320.0	220.0	100.0
44213000	PATCHING REINFORCEMENT	SQ YD	556.0		556.0
44213100	PAVEMENT FABRIC	SQ YD	100.0	40.0	60.0
44213200	SAW CUTS	FOOT	3,347.0	1047.0	2,300.0
44213208	TIE BARS 1 1/4"	EACH	266.0	60.0	206.0
67100100	MOBILIZATION	L SUM	1.0	0.3	0.7
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	12.0	4.0	8.0
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	0.3	0.7
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1.0	0.3	0.7
X0323583	SPEED INDICATOR SIGN	CAL DA	20.0	5.0	15.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	14.0	14.0

FILE NAME *	USER NAME * bucklesJJ	DESIGNED - RLA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\pwork\bucklesJJ\d0239130\0572878-sh1-500.dgn	DRAWN - RLA	REVISED -	39			57(2,3,4)PATCHING-1	MCLEAN	16	4	
PLOT SCALE = 40.0000 / IN.	CHECKED - JMS	REVISED -	CONTRACT NO. 70878							
PLOT DATE = 10/19/2010	DATE - 9/13/10	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA. N/A TO STA. N/A				