

SUMMARY OF QUANTITIES

LOCATION OF WORK				IL 104 80% FED / 20% STATE ROADWAY	IL 104 80% FED / 20% STATE STRUCTURE
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	0004	0011
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	87	87	
40600990	TEMPORARY RAMP	SQ YD	87	87	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	304	304	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	4198	4198	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	43	43	
44000100	PAVEMENT REMOVAL	SQ YD	816	816	
44000400	GUTTER REMOVAL	FOOT	1447	1447	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	45	45	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	86	86	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	128	128	
50200100	STRUCTURE EXCAVATION	CU YD	170		170
50300100	FLOOR DRAINS	EACH	12		12
50300225	CONCRETE STRUCTURES	CU YD	54		54
50300255	CONCRETE SUPERSTRUCTURE	CU YD	232		232
50300260	BRIDGE DECK GROOVING	SQ YD	500		500
50300280	CONCRETE ENCASEMENT	CU YD	4		4
50300300	PROTECTIVE COAT	SQ YD	590		590
50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48 in.	FOOT	531		531
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	57,690		57,690
50800515	BAR SPLICERS	EACH	568		568
51201400	FURNISHING STEEL PILES HP10X42	FOOT	300		300
51202305	DRIVING PILES	FOOT	300		300
51203400	TEST PILE STEEL HP10X42	EACH	2		2
51500100	NAME PLATES	EACH	1		1

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
c:\pwwork\pwwork\laughlinr1\0215213\d62698-sht-seq.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000' / in.		CHECKED -	REVISED -
PLOT DATE = Oct-14-2010 09:32:13AM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 104 OVER GRINDSTONE CREEK
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
745	107B-1	ADAMS	86	4
CONTRACT NO. 72B98			ILLINOIS FED. AID PROJECT	

Rev.