LOCATION (LT/RT) (STA)	TYPE OF ENTRANCE	EX MAT TYPE	EX WIDTH FOOT	WIDTH FOOT	AREA SQ YD	HMA 3-1/2" TON	VOLUME (AGG) CU YD	AGG 2" TON	HMA VD TON	PREP OF BASE SQ YD	HMA BUTT JOINT SQ YD	DRVWY PAVMNT REM. SQ YD
RT 319+50	PE	HMA/AGG	30	24	37.8	7.4	1.3	2.7		37.8		
RT 321+06	PE	HMA/AGG	49	24	37.8	7.4	1.3	2.7		37.8		
LT SUDDUTH RD.	SIDEROAD	HMA	22	22	35.6		N/A		4.0		14.7	
RT SUDDUTH RD.	SIDEROAD	HMA	22	22	35.6		N/A		4.0		14.7	
LT 375+50	MB	AGG	20	20	37.3	7.3	N/A					
RT 375+50	PE	AGG	44	24	37.8	7.4	1.3	2.7		37.8		
LT 378+21	PE	AGG	53	24	37.8	7.4	1.3	2.7		37.8		
LT 392+66	PE w/MB	HMA/AGG	53	24	60.0	11.8	1.3	2.7		60.0		
RT 394+51	PE	HMA/AGG	45	24	37.8	7.4	1.3	2.7		37.8		
LT 395+13	PE	HMA/AGG	45	24	37.8	7.4	1.3	2.7		37.8		
RT 397+26	PE	AGG	38	24	37.8	7.4	1.3	2.7		37.8		
RT 397+67	PE	AGG	32	24	37.8	7.4	1.3	2.7		37.8		
RT 399+09	PE	AGG	42	24	37.8	7.4	1.3	2.7		37.8		
RT 400+15	PE	AGG	36	24	37.8	7.4	1.3	2.7		37.8		
RT 402+74	PE	AGG	48	24	37.8	7.4	1.3	2.7		37.8		
RT 404+57	PE	HMA	32	24	37.8		N/A		4.2		16.0	
RT 405+07	PE	HMA/AGG	33	24	37.8	7.4	1.3	2.7		37.8		
LT 408+45	MB	HMA	18	18	35.0	6.9	N/A					
RT 408+48	PE	HMA/AGG	46	24	37.8	7.4	1.3	2.7		37.8		
LT 411+50	SIDEROAD	HMA/AGG	24	24	37.8	7.4	1.3	2.7		37.8	16.0	
LT 413+72	PE w/MB	HMA/AGG	50	24	60.0	11.8	1.3	2.7		60.0		
RT 430+20	PE	AGG	24	24	37.8	7.4	1.3	2.6		37.8		
LT 436+55	MB	HMA/AGG	4	4	15.6		N/A		1.7			
RT 436+62	PE	HMA/AGG	43	24	37.8	7.4	1.3	2.7		37.8		
RT 438+24	PE	HMA/AGG	18	18	31.1	7.0	1.1	2.2				
LT 438+52	MB	HMA/AGG	29	20	37.3	7.3	N/A					
RT 438+80	PE	HMA/AGG	18	18	31.1	7.0	1.1	2.2				
RT 440+19	PE	AGG	18	18	31.1	6.1	1.1	2.2		31.1		
LT 444+21	MB	HMA	19	19	32.3		N/A		3.6			
RT 444+21	PE	HMA/AGG	64	24	37.8	7.4	1.3	2.7		37.8		
LT 446+41	MB	HMA	18	18	31.9		N/A		3.6			
RT 446+41	PE	HMA/AGG	40	24	37.8	7.4	1.3	2.7		37.8		
LT 449+66	MB	HMA	18	18	31.9		N/A		3.6			
RT 449+66	PE	HMA/AGG	36	24	37.8	7.4	1.3	2.7		37.8		
LT 451+36	MB	HMA	20	20	32.7		N/A		3.7			
RT 451+36	PE	HMA/AGG	37	24	37.8	7.4	1.3	2.7		37.8		
LT 455+87	MB	HMA	44	44	91.6		N/A		10.3			
RT 455+87	PE	CONC	47	24	37.8				4.2			20.9
LT 456+57	PE w/MB	AGG	44	24	60.0	11.8	1.3	2.7		60.0		
LT 460+44	PE	HMA/AGG	48	24	37.8	7.4	1.3	2.7		37.8		
LT Barber Rd.	SIDEROAD	HMA	46	46	62.2		N/A		7.0			
RT Holten Rd.	SIDEROAD	HMA	50	50	66.7		N/A		7.5			
LT 474+37	PE	AGG	34	24	37.8	7.4	1.3	2.7		37.8		
LT 475+49	PE	AGG	34	24	37.8	7.4	1.3	2.7		37.8		
LT 497+93	PE w/MB	HMA	64	24	60.0	11.8	1.3	2.7		60.0	16.0	
LT 500+32	PE	HMA	29	24	37.8	7.4	1.3	2.7		37.8	16.0	
LT 511+65	PE w/MB	HMA	34	24	60.0	11.8	1.3	2.7		60.0	16.0	
LT 513+58	PE	HMA	58	24	37.8	7.4	1.3	2.7		37.8	16.0	
LT 517+38	PE w/MB	HMA	45	24	60.0	11.8	1.3	2.7		60.0	16.0	
LT 518+38	PE w/MB	HMA	48	24	60.0	11.8	1.3	2.7		60.0	16.0	
LT 519+56	PE	HMA	21	21	34.4	6.8	1.3	2.7		34.4	14.0	
LT 520+98	PE	HMA	25	24	37.8	7.4	1.3	2.7		37.8	16.0	
LT 522+24	PE w/MB	HMA/AGG	24	24	60.0	11.8	1.3	2.7		60.0		
Total					*2211.1*	*334.9*		*102.6*	*57.3*	*1527.8*	*187.3*	*20.9*

1 Added Sheet 1-10-11

FILE NAME = c:\pw_work\pwidot\baij\d0217723\ent_ppp.dgn	USER NAME = baij	DESIGNED -	REVISED - 2/19/03 JCN	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
ENT PPP.DGN		DRAWN - CADD	REVISED - 4/01/04 JCN	
	PLOT SCALE = 100.000 ' / IN.	CHECKED - JCN	REVISED -	
	PLOT DATE = Jan-06-2011 03:10:37PM	DATE - FEBRUARY 23, 1999	REVISED -	

DIST. 6 DETAILS FOR RURAL/URBAN ENT., MAILBOX TURNOUT & SIDEROADS W/O CONC. GUTTER (3P-PROJ.)

SCALE: | SHEET NO. 1 OF 3 SHEETS | STA. | TO STA.

F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
618	(B)RS-4, (0-15D)RS-2	SANGAMON	32	32a
		CONTRACT NO. 72D56		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT