

**Pavement marking quantity**

Location	Length of Roadway (feet)	Quantity (FOOT)		
		No Pass	Skip Dash	Edgeline
<b>Andrew Road</b>				
STA. 1074+47 to STA. 1076+19.1	172.10	160	23.025	344.2
STA. 1075+08.4 to STA. 1121+40.34	4631.94		1157.985	9263.88
STA. 1+00 to STA. 5+60.23	460.23	160	95.0575	920.46
<i>Andrew Rd Subtotal</i>		<i>320</i>	<i>1276</i>	<i>10529</i>
<b>IL 124</b>				
STA. 276+34 to STA. 368+98.90	9264.90	957.8	2196.5	18529.8
STA. 368+98.99.12 to 395+85.96	2686.97	5373.94		5373.94
STA. 396+39.54 to 420+32.31	2392.77	4785.54		4785.54
STA. 420+49.79 to 464+33.95	4384.16	8768.32		8768.32
STA. 465+00 to 522+50	5750.00	11500		11500
<i>IL 24 Subtotal</i>		<i>31386</i>	<i>2197</i>	<i>48958</i>
<b>Total</b>	<b>29743.07</b>	<b>31706</b>	<b>3473</b>	<b>59486</b>

**Raised reflective pavement marker quantity**

Location	Start Station	End Station	Length (FOOT)	Quantity (EACH)
<b>Andrew Road</b>				
	1074+47.	1076+19.1	172.10	2
	1075+08.4	1121+40.34	4631.94	58
	1+00.	5+60.23	460.23	6
<i>Andrew Rd Subtotal</i>			<i>5264.27</i>	<i>66</i>
<b>IL 124</b>				
	276+34.	368+98.9	9264.90	116
	368+98.99	395+85.96	2686.97	34
	396+39.54	420+32.31	2392.77	30
	420+49.79	464+33.95	4384.16	55
	465+00.	522+50.	5750.00	72
<i>IL 24 Subtotal</i>			<i>24478.80</i>	<i>306</i>
<b>Total</b>			<b>29743</b>	<b>372</b>

*Two-way amber markers needed*

**Shoulder Rumble Strip Quantity**

Location	Length of Roadway (FOOT)	Quantity (FOOT)
<b>IL 124</b>		
STA. 276+34 to STA. 368+98.90	9264.90	18529.8
STA. 368+98.99.12 to 395+85.96	2686.97	5373.94
STA. 396+39.54 to 420+32.31	2392.77	4785.54
STA. 420+49.79 to 464+33.95	4384.16	8768.32
STA. 465+00 to 522+50	5750.00	11500
<b>Total</b>	<b>24479</b>	<b>48958</b>