

PAVEMENT MARKING SCHEDULE

STATION	TYPE	PAINT PVT MK LINE 5"	
		WHITE	YELLOW
LT & RT 1770+36 TO 1797+50	EDGE LINE	5,428 FT	
RT 1770+36 TO 1793+18	NO PASS		2,282 FT
LT 1770+36 TO 1797+50	NO PASS		2,714 FT
RT 1793+18 TO 1797+50	SKIP DASH		110 FT
LT & RT 1905+79 TO 1957+15	EDGE LINE	10,272 FT	
1905+79 TO 1906+57	SKIP DASH		20 FT
RT 1906+57 TO 1916+01	NO PASS		944 FT
LT 1906+57 TO 1916+01	SKIP DASH		240 FT
LT 1916+01 TO 1925+80	NO PASS		1,979 FT
RT 1916+01 TO 1925+80	NO PASS		240 FT
1925+80 TO 1932+91	SKIP DASH		180 FT
RT 1932+91 TO 1944+34	NO PASS		1,143 FT
LT 1932+91 TO 1939+66	SKIP DASH		170 FT
LT 1939+66 TO 1951+89	NO PASS		1,223 FT
RT 1944+34 TO 1951+89	SKIP DASH		190 FT
RT 1916+01 TO 1925+80	SKIP DASH		130 FT
TOTALS		15,700 FT	11,565 FT

AGGREGATE SHOULDERS, TYPE B

STATION	
LT & RT 1905+79 TO 1957+15	195 TON
TOTALS	195.0 TON

NOTES:

STATIONS ARE APPROXIMATE.

QUANTITIES FOR THE SIDEROAD ARE INCLUDED IN HOT-MIX ASPHALT SURFACE COURSE AND HOT-MIX ASPHALT SURFACE REMOVAL.

MIXTURE REQUIREMENTS

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT

MIXTURE USE(S):	H.M.A S.C., MIX C, N70	PAVEMENT PATCHING
AC/PG	PG 64-22	PG 64-22
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 70	4.0% @ N DESIGN = 70
MIXTURE COMP:	IL 9.5 OR 12.5	IL 19.0
FRICION AGG:	MIX "C"	N/A

SCHEDULES
FAP 317 (US 24)
SECTION 2 RS-7
ADAMS COUNTY