



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 7, 2011

SUBJECT: FAI Route 64 (I-64)  
Project ACIM-064-1 (128) 009  
Section 82-5K-2  
St. Clair County  
Contract No. 76D59  
Item No. 126, January 21, 2011 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 5 - 8, 11, 16, 17, 20, 45 and 121 of the Plans.
3. Revised page 13 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Mike Renner; D. Carl Puzey;  
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
XX008423	PRECAST CONC LAGGING	SQ FT	863.000				
X0301271	REM EX UNDERDRAINS	FOOT	2,705.000				
X0321809	PERMANENT GRND ANCHOR	EACH	26.000				
X0323360	WOOD POLE REMOVAL	EACH	10.000				
X0323586	PIPE DRAIN REMOVAL	FOOT	96.000				
X0324085	EM VEH P S LSC 20 3C	FOOT	1,048.000				
X0324455	DRILL/SET SOLD P SOIL	CU FT	2,111.000				
X0325751	DRIVE SOLDIER PILES	FOOT	844.000				
X2020502	BRACED EXCAVATION	CU YD	64.000				
X4401980	CONC BARRIER REMOV	FOOT	52.000				
X6370279	CONC BAR 1F 42HT SPL	FOOT	28.000				
X7240605	REM RE-E BR MTD SIGN	EACH	1.000				
* X7800200	PAINT PVT MARK CURB	FOOT	595.000				
Z0007118	UNTREATED TIMBER LAG	SQ FT	1,049.000				
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0017202	DOWEL BARS 1 1/2	EACH	1,455.000				
* Z0018900	DRILL-GROUT DOW BARS	EACH	712.000				
Z0021906	SILICONE JT SEAL 1.5	FOOT	17.700				
Z0021908	SILICONE JT SEAL 2	FOOT	17.700				
Z0025100	F & I CABLE SPLICES	EACH	54.000				
Z0026402	FUR SOLDIER PILES HP	FOOT	1,517.000				
Z0030020	IMP ATTEN FRD NAR TL2	EACH	2.000				
Z0030240	IMP ATTN TEMP NRD TL2	EACH	4.000				
Z0030260	IMP ATTN TEMP FRN TL3	EACH	4.000				
Z0033084	EC C GROUND 6 1C GRN	FOOT	3,765.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	275.000				
Z0073200	TEMP SHORING & CRIB	EACH	1.000				
Z0075310	TIE BARS 3/4	EACH	342.000				
Z0076600	TRAINEES	HOUR	1,500.000		0.800		1,200.000
20100110	TREE REMOV 6-15	UNIT	450.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20100210	TREE REMOV OVER 15	UNIT	68.000				
20200100	EARTH EXCAVATION	CU YD	2,489.000				
20400800	FURNISHED EXCAVATION	CU YD	43,032.000				
20700220	POROUS GRAN EMBANK	CU YD	12.000				
25000200	SEEDING CL 2	ACRE	6.300				
25000400	NITROGEN FERT NUTR	POUND	564.000				
25000500	PHOSPHORUS FERT NUTR	POUND	564.000				
25000600	POTASSIUM FERT NUTR	POUND	564.000				
25100105	MULCH METHOD 1	ACRE	6.300				
25100630	EROSION CONTR BLANKET	SQ YD	18,717.000				
28000250	TEMP EROS CONTR SEED	POUND	1,253.000				
28000305	TEMP DITCH CHECKS	FOOT	286.000				
28000400	PERIMETER EROS BAR	FOOT	2,487.000				
28000500	INLET & PIPE PROTECT	EACH	4.000				
28100707	STONE DUMP RIP CL A4	SQ YD	1,060.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28200200	FILTER FABRIC	SQ YD	1,060.000				
35101100	AGG BASE CSE A 12	SQ YD	6,358.000				
35300410	PCC BSE CSE 9 1/2	SQ YD	1,187.000				
40600200	BIT MATLS PR CT	TON	32.600				
40600300	AGG PR CT	TON	90.800				
40600645	LEV BIND MM N90	TON	1,259.000				
40600985	PCC SURF REM BUTT JT	SQ YD	270.000				
40600990	TEMPORARY RAMP	SQ YD	345.000				
40603090	HMA BC IL-19.0 N90	TON	1,095.000				
40603570	P HMA SC "E" N90	TON	2,252.000				
40702001	HMA PAVT FD 16	SQ YD	3,705.000				
42001200	PAVEMENT FABRIC	SQ YD	890.000				
* 42001300	PROTECTIVE COAT	SQ YD	1,061.000				
44000100	PAVEMENT REM	SQ YD	66.000				
44000155	HMA SURF REM 1 1/2	SQ YD	1,038.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000157	HMA SURF REM 2	SQ YD	14,014.000				
44000500	COMB CURB GUTTER REM	FOOT	1,175.000				
44003100	MEDIAN REMOVAL	SQ FT	4,935.000				
44004250	PAVED SHLD REMOVAL	SQ YD	3,343.000				
44200569	CL A PATCH T3 11	SQ YD	25.000				
44200571	CL A PATCH T4 11	SQ YD	586.000				
44200970	CL B PATCH T2 10	SQ YD	495.000				
44200974	CL B PATCH T3 10	SQ YD	18.000				
44200976	CL B PATCH T4 10	SQ YD	387.000				
* 44213000	PATCH REINFORCEMENT	SQ YD	534.000				
44213200	SAW CUTS	FOOT	5,819.000				
44300200	STRIP REF CR CON TR	FOOT	4,028.000				
48100500	AGGREGATE SHLDS A 6	SQ YD	745.000				
48102100	AGG WEDGE SHLD TYPE B	TON	183.000				
48203029	HMA SHOULDERS 8	SQ YD	3,685.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR- -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
48203100	HMA SHOULDERS	TON	844.000				
50102400	CONC REM	CU YD	23.200				
50104650	SLOPE WALL REMOV	SQ YD	372.700				
50104720	REM EXIST CONC DECK	EACH	1.000				
50157300	PROTECTIVE SHIELD	SQ YD	106.000				
50200100	STRUCTURE EXCAVATION	CU YD	332.000				
50300225	CONC STRUCT	CU YD	190.500				
50300255	CONC SUP-STR	CU YD	225.500				
50300260	BR DECK GROOVING	SQ YD	513.000				
50300300	PROTECTIVE COAT	SQ YD	648.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	1,790.000				
50800205	REINF BARS, EPOXY CTD	POUND	87,270.000				
50800515	BAR SPLICERS	EACH	32.000				
50901730	BRIDGE FENCE RAILING	FOOT	223.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT  
NUMBER -

76D59

State Job # - C-98-037-10  
PPS NBR - 8-00264-0000  
County Name - ST CLAIR- -  
Code - 163 - -  
District - 8 - -  
Section Number - 82-5K-2

Project Number  
ACIM-0641/128/009

Route  
FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
51200957	FUR M S PILE 12X0.250	FOOT	1,068.000				
51202305	DRIVING PILES	FOOT	1,068.000				
51203200	TEST PILE MET SHELLS	EACH	3.000				
51500100	NAME PLATES	EACH	1.000				
52100010	ELAST BEARING ASSY T1	EACH	4.000				
52100520	ANCHOR BOLTS 1	EACH	14.000				
52100530	ANCHOR BOLTS 1 1/4	EACH	12.000				
542A1900	P CUL CL A 3 15	FOOT	116.000				
54213447	END SECTIONS 12	EACH	2.000				
54213660	PRC FLAR END SEC 15	EACH	2.000				
58600100	SAND BACKFILL	CU YD	94.000				
58700300	CONCRETE SEALER	SQ FT	2,835.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	195.000				
60100060	CONC HDWL FOR P DRAIN	EACH	17.000				
60100945	PIPE DRAINS 12	FOOT	216.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR- -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60107700	PIPE UNDERDRAINS 6	FOOT	5,858.000				
60108200	PIPE UNDERDRAIN 6 SP	FOOT	150.000				
60500060	REMOV INLETS	EACH	2.000				
* 60600605	CONC CURB TB	FOOT	72.000				
60602800	CONC GUTTER TB	FOOT	275.000				
60603500	COMB CC&G TB6.06	FOOT	147.000				
60607400	COMB CC&G TB9.24	FOOT	1,102.000				
60618300	CONC MEDIAN SURF 4	SQ FT	6,551.000				
60621200	CONC MED TSB9.24	SQ FT	60.000				
60900240	TY C INLET BOX 609006	EACH	2.000				
60900515	CONC THRUST BLOCKS	EACH	2.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	175.000				
63000003	SPBGR TY A 9FT POSTS	FOOT	150.000				
63000015	SPBGR TY D	FOOT	350.000				
63100085	TRAF BAR TERM T6	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR- -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63100167	TR BAR TRM T1 SPL TAN	EACH	3.000				
63200310	GUARDRAIL REMOV	FOOT	400.000				
63500105	DELINEATORS	EACH	36.000				
63700805	CONC BAR TRANS	FOOT	38.000				
67000400	ENGR FIELD OFFICE A	CAL MO	12.000				
67100100	MOBILIZATION	L SUM	1.000				
70100205	TRAF CONT-PROT 701401	EACH	2.000				
70100207	TRAF CONT-PROT 701402	EACH	1.000				
70100310	TRAF CONT-PROT 701421	L SUM	1.000				
70100420	TRAF CONT-PROT 701411	EACH	1.000				
70100430	TRAF CONT-PROT 701446	EACH	1.000				
70100700	TRAF CONT-PROT 701406	L SUM	1.000				
70100820	TRAF CONT-PROT 701451	L SUM	1.000				
70100825	TRAF CONT-PROT 701456	L SUM	1.000				
70102625	TR CONT & PROT 701606	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70102630	TR CONT & PROT 701601	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	365.000				
70300100	SHORT TERM PAVT MKING	FOOT	6,720.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	483.600				
70300220	TEMP PVT MK LINE 4	FOOT	24,502.000				
70300250	TEMP PVT MK LINE 8	FOOT	2,034.000				
70300260	TEMP PVT MK LINE 12	FOOT	779.000				
70300280	TEMP PVT MK LINE 24	FOOT	270.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	745.000				
* 70400100	TEMP CONC BARRIER	FOOT	2,183.500				
72000100	SIGN PANEL T1	SQ FT	107.250				
72000200	SIGN PANEL T2	SQ FT	44.000				
72000300	SIGN PANEL T3	SQ FT	660.750				
72400100	REMOV SIN PAN ASSY TA	EACH	11.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72400200	REMOV SIN PAN ASSY TB	EACH	8.000				
72400330	REMOV SIGN PANEL T3	SQ FT	1.000				
73000100	WOOD SIN SUPPORT	FOOT	181.000				
73302170	OSS CANT 2CA 3-0X5-6	FOOT	30.000				
73305000	OVHD SIN STR WALKWAY	FOOT	30.000				
73400200	DRILL SHAFT CONC FDN	CU YD	6.100				
78004200	PREF PL PM TB INL L&S	SQ FT	483.600				
78004210	PREF PL PM TB INL L4	FOOT	24,502.000				
78004240	PREF PL PM TB INL L8	FOOT	2,034.000				
78004250	PREF PL PM TB INL L12	FOOT	779.000				
78004280	PREF PL PM TB INL L24	FOOT	270.000				
78100100	RAISED REFL PAVT MKR	EACH	188.000				
78100105	RAISED REF PVT MKR BR	EACH	16.000				
78200300	PRISMATIC CURB REFL	EACH	92.000				
78200410	GUARDRAIL MKR TYPE A	EACH	22.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR- -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78201000	TERMINAL MARKER - DA	EACH	3.000				
78300200	RAISED REF PVT MK REM	EACH	151.000				
80300100	LOCATE UNDERGR CABLE	FOOT	5,240.000				
81000500	CON T 1 1/2 GALVS	FOOT	16.000				
81012300	CON T 1 PVC	FOOT	94.000				
81012400	CON T 1 1/4 PVC	FOOT	6.000				
81012500	CON T 1 1/2 PVC	FOOT	6.000				
81012600	CON T 2 PVC	FOOT	396.000				
81012700	CON T 2 1/2 PVC	FOOT	313.000				
81013000	CON T 4 PVC	FOOT	20.000				
81018500	CON P 2 GALVS	FOOT	506.000				
81018900	CON P 4 GALVS	FOOT	526.000				
81021550	CON AUGERED 2 PVC	FOOT	575.000				
81021570	CON AUGERED 3 PVC	FOOT	542.000				
81030100	CONDUIT SPLICE	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR- -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81100300	CON AT ST 1 GALVS	FOOT	60.000				
81100600	CON AT ST 2 GALVS	FOOT	188.000				
81300550	JUN BX SS AS 12X12X6	EACH	1.000				
81400100	HANDHOLE	EACH	8.000				
81400105	HANDHOLE SPL	EACH	2.000				
81400205	HD HANDHOLE SPL	EACH	3.000				
81400305	DBL HANDHOLE SPL	EACH	2.000				
81603025	UD 2#4 #4G XLPUSE 1	FOOT	2,872.000				
81603035	UD 2#6 #6G XLPUSE 1	FOOT	1,581.000				
81603065	UD 2#2#2G XLPUSE 1 1/4	FOOT	2,218.000				
81702415	EC C XLP USE 3-1C 6	FOOT	60.000				
81800190	A CBL 2-1C2 MESS WIRE	FOOT	2,500.000				
81800200	A CBL 2-1C4 MESS WIRE	FOOT	3,500.000				
81900200	TR & BKFIL F ELECT WK	FOOT	5,623.000				
82102400	LUM SV HOR MT 400W	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
83057220	LT P WD 40 CL 4	EACH	6.000				
83057440	LT P WD 80 CL 4	EACH	4.000				
83060550	LT P GS 50MH 15MA	EACH	4.000				
83600300	LIGHT POLE FDN 30D	FOOT	85.000				
83800205	BKWY DEV TR B 15BC	EACH	4.000				
84200804	REM POLE FDN	EACH	9.000				
84400105	RELOC EX LT UNIT	EACH	9.000				
87301215	ELCBL C SIGNAL 14 2C	FOOT	2,419.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	4,591.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	9,106.000				
87301805	ELCBL C SERV 6 2C	FOOT	60.000				
87502700	TS POST A 16	EACH	3.000				
87700150	S MAA & P 22	EACH	1.000				
87700260	S MAA & P 44	EACH	1.000				
87700280	S MAA & P 48	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87800100	CONC FDN TY A	FOOT	9.000				
87800200	CONC FDN TY D	FOOT	7.000				
87800400	CONC FDN TY E 30D	FOOT	10.000				
87800415	CONC FDN TY E 36D	FOOT	26.000				
87900200	DRILL EX HANDHOLE	EACH	9.000				
88020160	SH P 1F 3S BM	EACH	7.000				
88020170	SH P 1F 3S MAM	EACH	8.000				
88200300	TS BACKPLATE PLASTIC	EACH	10.000				
88500500	IND L DET AMP	EACH	2.000				
88600100	DET LOOP T1	FOOT	1,572.000				
89000100	TEMP TR SIG INSTALL	EACH	2.000				
89501100	RELOC EX TS CONT	EACH	2.000				
89501400	REL EM VEH PR SYS D U	EACH	1.000				
89502300	REM ELCBL FR CON	FOOT	1,439.000				
89502375	REMOV EX TS EQUIP	EACH	2.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76D59

State Job # - C-98-037-10  
 PPS NBR - 8-00264-0000  
 County Name - ST CLAIR - -  
 Code - 163 - -  
 District - 8 - -  
 Section Number - 82-5K-2

Project Number  
 ACIM-0641/128/009

Route  
 FAI 64

\* REVISED : JANUARY 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
89502380	REMOV EX HANDHOLE	EACH	6.000				
89502385	REMOV EX CONC FDN	EACH	3.000				

No separate measurement or payment will be made for Porous Granular Embankment placed between the two barriers, concrete caps over the fill, or joint filler; the costs of furnishing and constructing these items will be included in the contract unit price per foot for Concrete Barrier, Single Face, 42 Inch Height (Special).

Basis of Payment: This work shall be paid for at the contract unit price per foot for CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL). Polyethylene bond breaker, expansion joint filler, concrete and reinforcing steel shall not be measured for payment, but shall be considered included in this Item.

## **CONCRETE BARRIER TRANSITION**

Description: This work shall consist of constructing a section of concrete barrier to transition from the existing concrete barrier to the proposed bridge pier as shown on the plans. All work shall be performed per Section 637 of the Standard Specifications, and as modified herein.

Concrete Barrier Transition shall be cast-in-place using formwork. Concrete Median, 4" sloped to drain, will be used as a cap over Porous Granular Embankment.

In the transition section between Concrete Barrier, Single Face, 42 Inch Height (Special) and an existing bridge pier, the space between the reinforced concrete wall and the Concrete Barrier, Single Face, shall be formed with concrete.

The transition section shall be reinforced as a Concrete Barrier, Double Face, 42 Inch Height.

A key way may not be used in lieu of dowels.

Method of Measurement: Concrete Barrier Transition will be measured for payment in feet, in place, along the centerline of the transition section. Porous Granular Embankment will be measured per cubic yard and as Concrete Median Surface will be measured per square foot.

Basis of Payment: This work shall be paid for at the contract unit price per foot for CONCRETE BARRIER TRANSITION, per cubic yard for POROUS GRANULAR EMBANKMENT, and per square foot for CONCRETE MEDIAN SURFACE, 4 INCH.

## **DRILL AND GROUT DOWEL BARS**

Description: This work consists of furnishing and installing dowel bars at **longitudinal** construction joints located where a proposed concrete pavement or base ties into an existing concrete pavement or base. The embedment length and spacing of dowel bars shall be as detailed on the plans or as directed by the Engineer.

Materials: Dowel bars shall meet the requirements of Article 1006.11(b) in the Standard Specifications. Non-shrink grout shall meet the requirements of Article 1024.01. Chemical adhesive shall meet the requirements of Article 1027.01.

Construction Requirements: The dowel bars shall be installed in drilled holes along the vertical edge of the existing pavement or base as specified in Article 420.05(c) of the Standard Specifications. Load testing will not be required.

Revised 01/07/2011