



**HOT-MIX ASPHALT SHOULDERS, 8"**

MERIDIAN ROAD	
STA	HMA SHOULDERS 8" (SY)
284+13 to 301+97.81 (Lt & Rt)	2,379.7
307+67.81 to 340+86.80 (Lt & Rt)	4,425.3
340+86.80 to 351+36.31 (Lt)	686.5
340+86.80 to 349+64.14 (Rt)	584.9
414+57.84 to 417+62.09 (Lt)	202.8
414+57.84 to 417+62.09 (Rt)	202.8
423+04.34 to 425+85.11 (Lt)	187.2
456+86.03 to 460+04.54 (Rt)	212.3
469+81.33 to 472+84.32 (Lt)	202.1
129+44.73 to 134+63.69 (Rt)	312.7
<b>Sub-Total</b>	<b>9,396.4</b>

  

AUBURN ROAD	
STA	HMA SHOULDERS 8" (SY)
105+36 to 108+66	297.7
<b>Sub-Total</b>	<b>297.7</b>

  

CEMETERY ROAD	
STA	HMA SHOULDERS 8" (SY)
196+51 to 200+43.92 (Rt)	171.3
<b>Sub-Total</b>	<b>171.3</b>
<b>Total</b>	<b>9,865.4</b>

**PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 1 EQRS 36 (FT)
396+40	X-over	80.0
<b>Total</b>		<b>80.0</b>

**PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 48"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 1 EQRS 48 (FT)
401+52 to 402+84 (Auburn)	X-Over	128.0
<b>Total</b>		<b>128.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"**

MERIDIAN ROAD		
STA	O/S	PRC FL END S EQ RS 36 (EA)
396+40	Lt	1.0
396+40	Rt	1.0
<b>Total</b>		<b>2.0</b>

**PIPE CULVERT REMOVAL**

MERIDIAN ROAD		
STA	O/S	PIPE CULVERT REMOV (FT)
353+72	Rt	16.0
397+04	Rt	57.0
402+87	X-Over	61.0
431+85	Rt	34.0
433+09	X-Over	60.0
436+37 (at Safford)	X-Over	105.0
476+28 (at Dickenson)	X-Over	49.0
481+92	Lt	34.0
123+35	Lt	25.0
134+17	Rt	22.0
138+99	N/A	91.0
146+60	Lt	28.0
148+69	Rt	37.0
<b>Sub-Total</b>		<b>619.0</b>

  

AUBURN ROAD		
STA	O/S	PIPE CULVERT REMOV (FT)
99+41	X-Over	60.0
105+23	Lt	50.0
105+89 to 109+08	Lt	320.0
<b>Sub-Total</b>		<b>430.0</b>

  

DICKENSON ROAD		
STA	O/S	PIPE CULVERT REMOV (FT)
15+02	Rt	30.0
18+43	N/A	41.0
<b>Sub-Total</b>		<b>71.0</b>

  

CEMETERY ROAD		
STA	O/S	PIPE CULVERT REMOV (FT)
196+35	Lt	36.0
201+01	N/A	65.0
201+77	N/A	46.0
203+40	Lt	20.0
203+43	Rt	19.0
204+33	Rt	21.0
204+83	Rt	17.0
205+34	Rt	25.0
<b>Sub-Total</b>		<b>249.0</b>

**FLARED END SECTION REMOVAL**

MERIDIAN ROAD		
STA	O/S	FLARED END SEC REM (EA)
353+72	Rt	1.0
<b>Total</b>		<b>1.0</b>

  

PIPE CULVERTS, CLASS A, TYPE 1 12"		
STA	O/S	P CUL CL A T-1 12" (FT)
435+42 to 435+42	Rt	4.0
<b>Total</b>		<b>4.0</b>

**PIPE CULVERTS, CLASS A, TYPE 1 24"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 1 24 (FT)
396+44 to 397+68	Rt	112.0
138+51	X-Over	97.0
<b>Sub-Total</b>		<b>209.0</b>

  

DICKENSON ROAD		
STA	O/S	P CUL CL A 1 24 (FT)
19+00	X-Over	72.0
<b>Sub-Total</b>		<b>72.0</b>

  

CEMETERY ROAD		
STA	O/S	P CUL CL A 1 24 (FT)
202+13	N/A	120.0
<b>Sub-Total</b>		<b>120.0</b>
<b>Total</b>		<b>401.0</b>

**PIPE CULVERTS, CLASS A, TYPE 1 30"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 1 30 (FT)
396+44 to 397+68	Rt	112.0
138+51	X-Over	97.0
<b>Sub-Total</b>		<b>209.0</b>

  

DICKENSON ROAD		
STA	O/S	P CUL CL A 1 30 (FT)
19+00	X-Over	72.0
<b>Sub-Total</b>		<b>72.0</b>

  

CEMETERY ROAD		
STA	O/S	P CUL CL A 1 30 (FT)
202+13	N/A	120.0
<b>Sub-Total</b>		<b>120.0</b>
<b>Total</b>		<b>401.0</b>

**PIPE CULVERTS, CLASS A, TYPE 1 36"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 1 36 (FT)
432+94 to 433+31	N/A	64.0
432+91 to 432+94	Rt	8.0
<b>Total</b>		<b>72.0</b>

**PIPE CULVERTS, CLASS D, TYPE 1, 15"**

MERIDIAN ROAD		
STA	O/S	P CUL CL D 1 15 (FT)
481+92	Lt	48.0
148+69	Rt	52.0
<b>Sub-Total</b>		<b>100.0</b>

  

AUBURN ROAD		
STA	O/S	P CUL CL D 1 15 (FT)
<b>Sub-Total</b>		<b>0.0</b>

  

DICKENSON ROAD		
STA	O/S	P CUL CL D 1 15 (FT)
15+02	Rt	52.0
15+02	Lt	40.0
<b>Sub-Total</b>		<b>92.0</b>

  

CEMETERY ROAD		
STA	O/S	P CUL CL D 1 15 (FT)
196+35	Lt	54.0
203+40	Lt	49.0
203+43	Rt	36.0
204+33	Rt	44.0
204+83	Rt	24.0
205+34	Rt	48.0
<b>Sub-Total</b>		<b>255.0</b>

**PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"**

SAFFORD ROAD		
STA	O/S	P CUL CL A 1 EQRS 30 (FT)
1+72 to 1+78	X-Over	78.0
1+77 to 1+83	X-Over	78.0
<b>Total</b>		<b>156.0</b>

  

PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"		
STA	O/S	P CUL CL A 1 EQRS 42 (FT)
402+86	X-Over	112.0
402+89 to 403+39	Lt	56.0
434+76 to 435+40	Rt	57.0
435+43 to 1+79 (Safford)	Rt	76.0
<b>Total</b>		<b>301.0</b>

**PIPE CULVERTS, CLASS A, TYPE 2 30"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 2 30 (FT)
<b>Sub-Total</b>		<b>0.0</b>

  

LATHAM ROAD		
STA	O/S	P CUL CL A 2 30 (FT)
1+78	N/A	104.0
<b>Sub-Total</b>		<b>104.0</b>
<b>Total</b>		<b>104.0</b>

**PIPE CULVERTS, CLASS A, TYPE 3 24"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 3 24 (FT)
<b>Sub-Total</b>		<b>0.0</b>

  

CEMETERY ROAD		
STA	O/S	P CUL CL A 3 24 (FT)
200+46	N/A	128.0
<b>Sub-Total</b>		<b>128.0</b>
<b>Total</b>		<b>128.0</b>

**PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"**

AUBURN ROAD		
STA	O/S	P CUL CL A 1 EQRS 24 (FT)
104+70 to 104+80	Lt	6.1
104+82 to 105+91	Lt	110.0
105+98 to 108+86	Lt	289.0
<b>Total</b>		<b>405.1</b>

**PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 1 EQRS 30 (EA)
396+44	Rt	1.0
397+75	Rt	1.0
400+49	Rt	1.0
403+31	Rt	1.0
403+44	Lt	1.0
435+43	Rt	1.0
<b>Sub-Total</b>		<b>4.0</b>

**PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"**

MERIDIAN ROAD		
STA	O/S	P CUL CL A 1 EQRS 42 (FT)
402+86	X-Over	112.0
402+89 to 403+39	Lt	56.0
434+76 to 435+40	Rt	57.0
435+43 to 1+79 (Safford)	Rt	76.0
<b>Total</b>		<b>301.0</b>

**PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"**

MERIDIAN ROAD		
STA	O/S	P CUL CL D 1 EQRS 24 (FT)
431+85	Rt	38.0
120+50	Rt	60.0
146+60	Lt	38.0
<b>Sub-Total</b>		<b>136.0</b>

  

AUBURN ROAD		
STA	O/S	P CUL CL D 1 EQRS 24 (FT)
105+38	Rt	57.0
<b>Sub-Total</b>		<b>57.0</b>

  

LATHAM ROAD		
STA	O/S	P CUL CL D 1 EQRS 24 (FT)
1+20	Rt	28.0
<b>Sub-Total</b>		<b>28.0</b>
<b>TOTAL</b>		<b>221.0</b>

**PIPE CULVERTS, CLASS D, TYPE 2 EQUIVALENT ROUND-SIZE 24"**

MERIDIAN ROAD		
STA	O/S	P CUL CL D 2 EQRS 24 (FT)
123+62	Lt	75.0
<b>Total</b>		<b>75.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"**

MERIDIAN ROAD		
STA	O/S	PRC FLAR END SEC 12 (EA)
353+74	Rt	1.0
397+75	Rt	1.0
400+49	Rt	1.0
403+31	Rt	1.0
403+44	Lt	1.0
435+43	Rt	1.0
<b>Total</b>		<b>7.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"**

MERIDIAN ROAD		
STA	O/S	PRC FLAR END SEC 24 (EA)
1+72	Lt	1.0
1+77	Lt	1.0
<b>Sub-Total</b>		<b>2.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"**

AUBURN ROAD		
STA	O/S	PRC FLAR END SEC 24 (EA)
105+38	Rt	2.0
<b>Sub-Total</b>		<b>2.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"**

DICKENSON ROAD		
STA	O/S	PRC FLAR END SEC 24 (EA)
19+00	Lt	1.0
19+00	Rt	1.0
<b>Sub-Total</b>		<b>2.0</b>

  

CEMETERY ROAD		
STA	O/S	PRC FLAR END SEC 24 (EA)
200+46	N/A	2.0
202+13	N/A	2.0
<b>Sub-Total</b>		<b>4.0</b>
<b>TOTAL</b>		<b>10.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"**

LATHAM ROAD		
STA	O/S	PRC FLAR END SEC 30 (EA)
1+78	Rt	1.0
1+78	Lt	1.0
<b>Total</b>		<b>2.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"**

MERIDIAN ROAD		
STA	O/S	PRC FLAR END SEC 36 (EA)
432+91	Rt	1.0
433+31	Lt	1.0
<b>Total</b>		<b>2.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"**

AUBURN ROAD		
STA	O/S	PRC FL END S EQ RS 24 (EA)
104+70	Lt	1.0
108+90	Lt	1.0
<b>Total</b>		<b>2.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"**

MERIDIAN ROAD		
STA	O/S	PRC FL END S EQ RS 30 (EA)
<b>Sub-Total</b>		<b>0.0</b>

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"**

SAFFORD ROAD		
STA	O/S	PRC FL END S EQ RS 36 (EA)
1+72	Lt	1.0
1+77	Lt	1.0
<b>Sub-Total</b>		<b>2.0</b>
<b>TOTAL</b>		<b>2.0</b>

**METAL END SECTIONS, EQUIVALENT ROUND-SIZE 24"**

MERIDIAN ROAD		
STA	O/S	MET END SEC EQV RS 24 (EA)
431+85	Rt	2.0
120+50	Rt	2.0
123+62	Lt	2.0
146+60	Lt	2.0
<b>Sub-Total</b>		<b>8.0</b>

**METAL END SECTIONS, EQUIVALENT ROUND-SIZE 24"**

AUBURN ROAD		
STA	O/S	MET END SEC EQV RS 24 (EA)
105+38	Rt	2.0
<b>Sub-Total</b>		<b>2.0</b>

  

LATHAM ROAD		
STA	O/S	MET END SEC EQV RS 24 (EA)
1+20	Rt	2.0
<b>Sub-Total</b>		<b>2.0</b>
<b>TOTAL</b>		<b>12.0</b>

**METAL END SECTIONS 15"**

MERIDIAN ROAD		
STA	O/S	MET END SEC 15 (EA)
481+92	Lt	2.0
148+69	Rt	2.0
<b>Sub-Total</b>		<b>4.0</b>

**METAL END SECTIONS 15"**

AUBURN ROAD		
STA	O/S	MET END SEC 15 (EA)
<b>Sub-Total</b>		<b>0.0</b>

  

DICKENSON ROAD		
STA	O/S	MET END SEC 15 (EA)
15+02	Rt	2.0
15+02	Lt	2.0
<b>Sub-Total</b>		<b>4.0</b>

**METAL END SECTIONS 15"**

||
||
||