



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 13, 2011

SUBJECT: Various Routes
Project HPP-0623(107)
Section 06-00002-00-PV (NIU)
DeKalb County
Contract No. 87476
Item 93
January 21, 2011 Letting
Addendum (D)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Index of Special Provisions, page 24 of the special provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott Stitt
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "DE" monogram.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation



Table of Contents

LOCATION OF PROJECT..... 2

DESCRIPTION OF WORK..... 2

COMPLETION DATE..... 2

TRAFFIC CONTROL PLAN..... 3

SEQUENCE OF WORK/MAINTENANCE OF TRAFFIC 4

SAW CUTTING OF PAVEMENT 5

TOPSOIL STRIPPING AND STOCKPILING..... 5

STEEL CASING PIPE..... 6

MANHOLE, SANITARY, TYPE 1 FRAME CLOSED LID 6

DROP SANITARY MANHOLES, TYPE 1 FRAME, CLOSED LID 6

SANITARY SEWER 8" 7

SANITARY SEWER 12" 7

SANITARY SEWER CONNECTION 7

SANITARY SEWER SERVICE..... 7

PORTLAND CEMENT CONCRETE SIDEWALK 7

DETECTABLE WARNINGS 8

CONSTRUCTION LAYOUT 8

EMBANKMENT..... 10

HOT MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS..... 10

AGGREGATE SHOULDERS TYPE B..... 12

PREPARATION OF BASE 12

CONTRACTOR ACCESS..... 13

PAVEMENT MARKING REMOVAL/WORK ZONE PAVEMENT MARKING REMOVAL..... 13

GENERAL ELECTRICAL REQUIREMENTS..... 13

LIGHT POLE..... 14

LUMINAIRE..... 15

LIGHTING CONTROLLER 15

CABLE IN RACEWAY, 15KV 16

CONDUIT ENCASED REINFORCED CONCRETE, 5" DIA. 17

LIGHT POLE FOUNDATION..... 18

ELECTRIC MANHOLE 18

TRANSFORMER 19

ELECTRIC SERVICE INSTALLATION 21

PLANTING WOODY PLANTS..... 21

CONCRETE MEDIAN, TYPE SB 21

SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL 22

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 22

TRANSMISSION TOWER PROTECTION..... 22

SANITARY MANHOLES TO BE ADJUSTED 22

SANITARY MANHOLES TO BE RECONSTRUCTED..... 22

WASHOUT BASIN..... 23

MOWING..... 23

RECONSTRUCT ELECTRIC MANHOLE 23

TOPSOIL 24

CAOD DATA 24

MANHOLE FRAME DETAIL 25

Phase II NPDES SWPPP 26



Basis of Payment: This work will be paid for at the contract unit price per EACH for RECONSTRUCT ELECTRIC MANHOLE.

TOPSOIL

This work shall consist of placing topsoil. Topsoil shall be placed in accordance to Article 211.04 and 211.05. Topsoil shall be placed in all locations intended to establish ground cover. Topsoil shall be placed in areas of storm water detention, on top of embankment, in graded channels, between the sidewalk and back of curb, above the still water level in storm water retention basins, and in restored trench backfill that is outside of the proposed roadways. Topsoil shall not be placed in areas of proposed pavement and below the still water level in storm water retention basins. Topsoil shall be placed, a minimum of 4-inches thick or the thickness as indicated in the typical sections, in a settled but non-compacted state.

Basis of Payment: The placement of topsoil will be incidental to TOPSOIL EXCAVATION AND PLACEMENT.

CADD DATA

CADD data will be available to the awarded Contractor. This information will be provided upon request as MicroStation CADD files and GeoPak coordinate geometry files only. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the Local Agency to request these files.

Revised 1-13-2011