


DRAINAGE SCHEDULE - STORM SEWER

STATION / LOCATION	20800150		54249510		550A0050		550A0340		55100500		Z0056648		Z0056668	
	TRENCH BACKFILL (CLSM UNDER ALL PAVEMENT AREAS)		CONCRETE COLLAR		STORM SEWERS, CLASS A, TYPE 1 12"		STORM SEWERS, CLASS A, TYPE 2 12"		STORM SEWER REMOVAL 12"		STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"		STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	
	(CU YD)		(CU YD)		(FOOT)		(FOOT)		(FOOT)		(FOOT)		(FOOT)	
FOURTH ST. AND JOHN ST.														
STR. #4	TO	STR. #6	RT.	22.0					55.7		55.7			
STR. #1	TO	STR. #4	RT.	20.3					51.3		51.3			
STR. #2	TO	STR. #3	LT.	20.1		50.8			50.8					
STR. EX. (4+15.78)	TO	STR. #8	LT.	20.7		52.2			52.2					
STR. EX. (4+25.61)	TO	STR. #5	RT.	1.2							7.2			
STR. #5	TO	STR. #7	RT.	6.7							41.9			
STR. #8	TO	STR. #9	LT.	0.7		4.2								
FOURTH ST. AND DANIEL ST.														
STR. #10	TO	STR. #12	LT.	8.2							51.0			
STR. #11	TO	STR. #11	RT.	3.5	1		6.0		6.0					
STR. #11	TO	STR. #11	RT.	3.5	1		6.0		6.0					
STR. EX. (4+63.88)	TO	STR. EX. (4+75.71)	LT.	3.1					13.3					
STR. EX. (4+64.92)	TO	STR. EX. (4+76.38)	RT.	3.2					13.5					
STR. #14	TO	STR. EX. (4+77.23)	RT.	1.9		11.8								
STR. #12	TO	STR. EX. (4+76.58)	LT.	0.9							5.6			
STR. EX. (5+15.77)	TO	STR. #13	RT.	4.7				12.4			11.0			
STR. EX. (5+15.74)	TO	STR. #18	LT.	11.1		69.1								
STR. #17	TO	STR. #18	L./RT	5.6		35.1								
FOURTH ST. AND CHALMERS ST.														
STR. #20	TO	STR. #21	-	6.7							42.0			
STR. #21	TO	STR. #24	LT.	8.7									54.5	
STR. EX. (6+65.11)	TO	STR. EX. (6+75.46)	RT.	3.1					13.1					
STR. #25	TO	STR. EX. (6+76.28)	RT.	1.8		11.3								
STR. EX. (6+74.41)	TO	STR. EX. (6+76.28)	RT.	4.1					17.3					
STR. EX. (17+15.22)	TO	STR. #23	RT.	3.0		18.5								
STR. EX. (17+15.22)	TO	STR. EX. (17+23.31)	RT.	5.0					21.4					
STR. #28	TO	STR. #28	LT.	3.2	1	6.0			6.0					
STR. #28	TO	STR. #28	LT.	3.2	1	6.0			6.0					
STR. #29	TO	STR. #29	RT.	2.4	1	6.0			6.0					
STR. #29	TO	STR. #29	RT.	2.4	1	6.0			6.0					
STR. #27	TO	STR. #26	RT.	1.2		7.6								
FOURTH ST. AND ARMORY AVE.														
STR. #30	TO	STR. EX. (7+78.67)	LT.	22.4		56.2			57.0					
STR. #31	TO	STR. #31	RT.	1.0	1						6.0			
STR. EX. (7+64.23)	TO	STR. EX. (7+78.40)	LT.	3.4					14.5					
STR. EX. (7+66.34)	TO	STR. EX. (7+79.12)	RT.	3.9					16.7					
STR. #33	TO	STR. EX. (7+78.94)	LT.	1.4		8.7								
STR. #34	TO	STR. EX. (7+79.12)	RT.	1.5		9.4								
STR. #35	TO	STR. #34	RT.	7.5							46.8			
STR. #37	TO	STR. EX. (18+51.56)	LT.	1.2	1	7.6								
STR. EX. (18+45.22)	TO	STR. EX. (18+56.49)	LT.	2.9					12.3					
STR. #36	TO	STR. EX. (18+51.71)	RT.	1.2	1	7.5								
STR. EX. (18+45.37)	TO	STR. EX. (18+52.71)	RT.	2.9					12.3					
STR. #37	TO	STR. #38	LT.	4.2		26.0								
TOTAL				235.5	9.0	400.0	12.0	449.8	318.5	54.5				

FILE NAME = I:\champaign\100940180\draw\cadd\sheet5
 USER NAME = Jim Michael
 2005-Sched\Juan-4thStreet.dgn
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 10/18/2010

DESIGNED - MWD
 DRAWN - RAH
 CHECKED - JMM
 DATE - 10/15/2010



**CITY OF CHAMPAIGN
 DEPARTMENT OF PUBLIC WORKS**

**SITE IMPROVEMENT PLAN
 FOURTH STREET IMPROVEMENT
 CHAMPAIGN, ILLINOIS**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7171	10-00285-00-SP	CHAMPAIGN	55	18
SCALE:			SHEET NO. OF SHEETS STA. TO STA.	
ILLINOIS FED. AID PROJECT				

CONTRACT NO. 91445