

PAVEMENT MARKING SCHEDULE

LOCATION	DESCRIPTION	PPP - TY B INLAID L & S	TPM - LINE 5' WHITE	TPM - LINE 5' YELLOW	TPM - DOUBLE LINE 5' YELLOW	TPM - LINE 6' WHITE	TPM - LINE 24' WHITE	TPM - LINE 12' WHITE	TPM - LINE 12' YELLOW	
										SQ FT
MEADOWBROOK ROAD										
STA 2+54 TO STA 9+56, 13.5' LT	LEFT EDGE PVMT		702							
STA 2+54 TO STA 9+52, 13.5' RT	RIGHT EDGE PVMT		698							
STA 2+54 TO STA 7+95, 4.5' LT	CENTERLINE				1082					
STA 7+95 TO STA 8+47.5, 4.5' LT	CENTERLINE TAPERS				210					
STA 7+95 TO STA 9+52	DIAGONALS								13	
STA 8+47.5 TO STA 9+52, 3.0' & 6.0' LT	CENTERLINE				428					
STA 9+52	STOP BAR						24			
STA 10+59 TO STA 25+26, 18.0' LT	LEFT EDGE PVMT		1467							
STA 10+59 TO STA 32+84, VARIES 9.0' RT TO 18.0' RT	RIGHT EDGE OF PAVEMENT		2225							
STA 10+59 TO STA 13+72, VARIES 13.0' RT TO 22.0' RT	EDGE BIKE LANE		313							
STA 10+59 TO STA 13+72, VARIES 13.0' RT TO 22.0' RT	DIAGONALS RIGHT OF BIKE LANE								117	
STA 10+63.5 TO STA 13+72, 6.0' LT & VARIES 3.0' LT TO 6.0	CENTERLINE				1244					
STA 10+63.5 LT	STOP BAR						18			
STA 10+63.5 TO STA 13+72	DIAGONALS ALONG CENTERLINE								80	
STA 13+72 TO STA 18+00, 6.0' LT	EDGE LINE			428						
STA 13+72 TO STA 18+00, 6.0' LT	SKIP-DASH			100						
STA 13+72 TO STA 18+00, 6.0' RT	EDGE LINE			100						
STA 13+72 TO STA 18+00, 6.0' RT	SKIP-DASH			100						
STA 18+00 TO STA 22+67.3, 6.0' RT	EDGE LINE				935					
STA 18+00 TO STA 25+26.3, 6.0' LT	EDGE LINE				1453					
STA 22+67.3 TO STA 25+26.3, 6.0' RT TO 6.0' LT	TAPER				288					
STA 24+11.32 TO STA 25+26.32, 6.0' RT	LANE LINE					115				
STA 18+00 TO STA 25+26	DIAGONALS ALONG CENTERLINE								295	
STA 25+91.3 TO STA 32+83.74, 6.0' LT	LANE LINE				1392					
STA 25+91.3 TO STA 30+24.78, 6.0' RT	LANE LINE				874					
STA 30+24.78 TO STA 31+68.78, 6.0' RT TO 6.0' LT	TAPER				288					
STA 31+68.78 TO STA 32+83.78, 6.0' RT	LANE LINE					115				
STA 25+91 TO STA 31+68	DIAGONALS ALONG CENTERLINE								278	
STA 25+97.32 TO STA 32+88.06, 18.0' LT	LEFT EDGE PVMT/BIKE LANE		691							
STA 32+84.06	STOP BAR						28			
STA 32+88.06	CROSS WALK				48					
STA 32+94.06	CROSS WALK				51					
STA 33+61.94	CROSS WALK				37					
STA 33+67.94	CROSS WALK				34					
STA 33+71.94	STOP BAR						21			
STA 33+71.94 TO STA 34+86.94, 5.0' LT	LANE LINE					115				
STA 33+71.94 TO STA 35+76.94, 5.0' RT TO 0.0' RT	CENTERLINE				410					
STA 34+86.94 TO STA 35+76.94	SKIP-DASH					24				
STA 14+64.00, STA 14+96.00, STA 16+78.00, STA 17+10.00, STA 24+211.32, STA 24+96.32, STA 31+68.78, STA 31+83.78, STA 34+00.77, STA 34+75.77	LEFT TURN ARROWS	156								
STA 2+65 TO STA 9+25 APPROX 220' SPACE	BIKE SYMBOLS BOTH SIDES	136								
STA 10+95 TO STA 15+60, SPACE AS SHOWN	BIKE SYMBOLS BOTH SIDES	136								
STA 16+75 TO STA 25+15, APPROX 215' SPACES	BIKE SYMBOLS BOTH SIDES	136								
STA 26+04 TO STA 32+75, APPROX 220' SPACES	BIKE SYMBOLS BOTH SIDES	136								
ILES AVENUE										
STA 459+12.62	CROSS WALK					66				
STA 459+18.62	CROSS WALK					74				
STA 460+23.62	CROSS WALK					65				
STA 460+29.62	CROSS WALK					56				
STA 459+00 TO STA 459+13	RIGHT EDGE LINE		13							
STA 459+00 TO STA 459+46.62	LEFT EDGE LINE		64							
STA 459+81.62 TO STA 460+49.49	LEFT EDGE LINE		85							
STA 460+29.62 TO STA 460+49.49	RIGHT EDGE LINE		20							
STA 460+29.62 TO STA 460+49.49	BIKE LANE		20							
STA 459+00 TO STA 459+46.62	DIAGONALS								49	
STA 459+81.62 TO STA 460+49.49	DIAGONALS								112	
STA 460+29.62 TO STA 459+49.49	DIAGONAL								15	
STA 9+55.88	CROSS WALK					64				
STA 9+61.88	CROSS WALK					57				
STA 10+53.5	CROSS WALK					70				
STA 10+59.5	CROSS WALK					67				
STA 460+49.49 TO STA 462+09.49	NORTH EDGE LINE	160								
STA 461+14.49 TO STA 462+09.49	CENTERLINE				380					
STA 460+49.49 TO STA 462+09.49	DIAGONALS								137	
STA 461+14.49 TO STA 462+09.49	DIAGONALS									9
McGREGOR										
STA 25+61.98, 33.5' LEFT	CROSS WALK					33				
STA 25+61.48, 38.5' LEFT	CROSS WALK					28				
STA 25+61.98, 44' LEFT	STOP BAR						14			
GREENBRIAR ROAD										
STA 9+05.84 TO STA 9+55.84	RIGHT EDGE LINE		50							
STA 9+05.84 TO STA 9+55.84	CENTERLINE				100					
STA 9+05.84 TO STA 9+55.84	LEFT EDGE LINE		50							
STA 9+55.84	STOP BAR									19
STA 9+60.5	CROSS WALK					40				
STA 9+66.5	CROSS WALK					45				
STA 10+33.5	CROSS WALK					43				
STA 10+39.5	CROSS WALK					38				
STA 10+43.77	STOP BAR								19	
STA 10+43.77 TO STA 10+93.77	RT/LT EDGE LINE S		100							
STA 10+43.77 TO STA 10+93.77	CENTERLINE				100					
TOTALS		700	16898	1293	143	1103				

PAVING SCHEDULE

LOCATION	CCC & G TY B-6.18	HMA PAVEMENT (FULL- DEPTH) 10"	SUB-BASE GRAN MATL TY A 12"	HMA PAVEMENT (FULL- DEPTH) 8 1/2"	PROCESSING LIME MODIFIED SOIL 12"	LIME
STA 9+23.64 TO STA 10+81.14	318	1708	1817	-	-	-
STA 10+81.14 TO STA 13+00.00	220	-	-	1095	1170	23.4
STA 13+00.00 TO STA 18+00.00	781*	-	-	2444	2709	54.2
STA 18+00.00 TO STA 23+00.00	1000	-	-	2444	2787	55.7
STA 23+00.00 TO STA 28+00.00	1012	-	-	2555	2901	58.0
STA 28+00.00 TO STA 33+94.97	1100	-	-	2569	2915	58.3
TOTAL	4431	1708	1817	11107	12482	250

* INCLUDES QUANTITY FROM ENTRANCE SCHEDULE
 ** INCLUDES NORTH SIDE OF GREENBRIAR ROAD

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	TPM L & S	TPM - LINE 5' WHITE	TPM - LINE 5' YELLOW	TPM - DOUBLE LINE 5' YELLOW	TPM - LINE 6' WHITE	TPM - LINE 24' WHITE	TPM - LINE 12' WHITE	TPM - LINE 12' YELLOW
MEADOWBROOK ROAD								
STA 2+54 TO STA 9+56, 13.5' LT		702						
STA 2+54 TO STA 9+52, 13.5' RT		698						
STA 2+54 TO STA 7+95, 4.5' LT				1082				
STA 7+95 TO STA 8+47.5, 4.5' LT				210				
STA 7+95 TO STA 9+52								13
STA 8+47.5 TO STA 9+52, 3.0' & 6.0' LT				428				
STA 9+52						24		
STA 10+59 TO STA 16+70, 18.0' LT		611						
STA 10+59 TO STA 16+70		611						
STA 10+59 TO STA 13+72, VARIES 13.0' RT TO 22.0' RT		313						
STA 10+59 TO STA 13+72, VARIES 13.0' RT TO 22.0' RT								117
STA 10+63.5 TO STA 13+72, 6.0' LT & VARIES 3.0' LT TO 6.0				1244				
STA 10+63.5 LT						18		
STA 10+63.5 TO STA 13+72								80
STA 13+72 TO STA 16+70, 6.0' LT			298					
STA 13+72 TO STA 16+70, 6.0' LT			70					
STA 13+72 TO STA 16+70, 6.0' RT			298					
STA 13+72 TO STA 16+70, 6.0' RT			70					
STA 14+64.00, STA 14+96.00,	31.2							
ILES AVENUE								
STA 459+12.62					66			
STA 459+18.62					74			
STA 460+23.62					65			
STA 460+29.62					56			
STA 459+00 TO STA 459+13		13						
STA 459+00 TO STA 459+46.62		64						
STA 459+81.62 TO STA 460+49.49		85						
STA 460+29.62 TO STA 460+49.49		20						
STA 460+29.62 TO STA 460+49.49		20						
STA 459+00 TO STA 459+46.62								49
STA 459+81.62 TO STA 460+49.49								112
STA 460+29.62 TO STA 459+49.49								15
STA 9+55.88					64			
STA 9+61.88					67			
STA 10+53.5					70			
STA 10+59.5					67			
STA 460+49.49 TO STA 462+09.49		160						
STA 461+14.49 TO STA 462+09.49								137
STA 460+49.49 TO STA 462+09.49								9
STA 461+14.49 TO STA 462+09.49	31		7377		529	42		532

SHORT-TERM PAVEMENT MARKING SCHEDULE

LOCATION	DESCRIPTION	TPM	TPM - LINE	TPM - LINE	TPM -
		L & S	5' WHITE	5' YELLOW	DOUBLE
		SQ FT	FOOT	FOOT	LINE 5' YELLOW
MEADOWBROOK ROAD					
STA 2+54 TO STA 9+56, 13.5' LT	LEFT EDGE PVMT		68		
STA 2+54 TO STA 9+52, 13.5' RT	RIGHT EDGE PVMT		68		
STA 2+54 TO STA					