

SIGN						
STATION	SIGN CODE	SIGN PANEL -	SIGN PANEL -	METAL SIGN	METAL SIGN	POST, SPECIAL
		TYPE 1	TYPE 2	POST - TYPE A	POST - TYPE B	
		SQ FT	SQ FT	FOOT	FOOT	EACH
▪	W2-6	6.25		32		
▪	W13-1	1.13				
▪	DIA. SIGN EASTBOUND		16		30	
17+74.24	W3-2	9.00		30		
18+93.96	R4-7	5.00				1
18+98.44	W11-2A	6.25				1
18+98.44	W16-7P	2.00				
19+14.52	W11-2A	6.25				1
19+14.52	W16-7P	2.00				
19+23.16	R1-2	3.90				1
19+81.09	R6-1R	3.00			12	
19+93.22	R6-1R	3.00			12	
20+18.91	R6-1R	3.00			12	
20+74.73	R1-2	3.90				1
20+84.41	W11-2A	6.25				1
20+84.41	W16-7P	2.00				
21+01.94	W11-2A	6.25				1
21+01.94	W16-7P	2.00				
21+06.49	R4-7	5.00				1
22+23.75	W3-2	9.00		30		
▪	DIA. SIGN WESTBOUND		16		30	
▪	W2-6	6.25		32		
▪	W13-1	1.13				
50+76.63	R1-2	3.90				1
50+85.53	W11-2A	6.25				1
50+85.53	W16-7P	2.00				
51+00.91	W11-2A	6.25				1
51+00.91	W16-7P	2.00				
51+06.27	R4-7	5.00				1
52+25.51	W3-2	9.00		30		
▪	DIA SIGN SOUTHBOUND		12		28	
▪	W2-6	6.25		32		
▪	W13-1	1.13				
	UNROUNDED TOTAL:	134.34				
	TOTALS:	135	44	186	124	12

• SEE PLANS FOR SPECIFIC SIGN LOCATIONS

PAVEMENT MARKING									
STATION	DESCRIPTION	THERMOPLASTIC PAVEMENT MARKING					TEMPORARY PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING CURB	PRISMATIC CURB REFLECTOR
		LETTERS AND SYMBOLS	LINE 4"	LINE 8"	LINE 12"	LINE 24"			
		SQ FT	FOOT	FOOT	FOOT	FOOT			
17+65.00 TO 19+39.41	SPLITTER ISLAND		298		47				
18+88.50 TO 19+35.85	RAISED ISLAND						102	17	
19+02.91 TO 19+16.79	SOLID WHITE CROSSWALK					70			
19+24.55 TO 19+32.44	WHITE YIELD BAR	15							
19+38.49 TO 19+52.44	WHITE 3' - 3' DASH			18					
19+57.16 TO 50+47.20	TEMPORARY PAINT WHITE						126		
19+57.16 TO 50+47.20	TEMPORARY PAINT YELLOW						129		
20+48.62 TO 20+60.90	WHITE 3' - 3' DASH			18					
20+60.89 TO 22+34.98	SPLITTER ISLAND		295		43				
20+64.23 TO 21+11.49	RAISED ISLAND						103	17	
20+67.29 TO 20+75.11	WHITE YIELD BAR	15							
20+82.80 TO 20+95.78	SOLID WHITE CROSSWALK					70			
50+49.60 TO 50+61.66	WHITE 3' - 3' DASH			18					
50+60.57 TO 52+35.00	SPLITTER ISLAND		298		48				
50+64.22 TO 51+11.49	RAISED ISLAND						100	17	
50+67.82 TO 50+75.78	WHITE YIELD BAR	15							
50+83.20 TO 50+97.11	SOLID WHITE CROSSWALK					70			
	TOTALS:	45	891	54	138	210	255	305	51

LAST SAVED = 11/1/2010
PEN TABLE = VB-HotF.tbl
PLOT DRIVER = TR-VBpdf-Black-HotF.plt

FILE NAME = \\0812900\cadd\pl\plans\05.D8XXXX-Sht-Schedule.dgn

USER NAME = sdonahue
PLOT SCALE = 40.0010 ' / IN.
PLOT DATE = 11/4/2010 11:7:00 PM

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -



SCHEDULES OF QUANTITIES
SCALE: NTS SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.U. 9170
PORTER / SIMMONS ROADS
SECTION 08-00060-00-PV
CONTRACT 97408

TOTAL SHEETS 36 SHEET NO. 9