

FAU ROUTE	SECTION	COUNTY
9257	06-00011-02-RP	ST CLAIR
CONTRACT NO. 97448		ILLINOIS

THOUVENOT, WADE & MOERCHEN, INC.
ENGINEERS SURVEYORS PLANNERS



- CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
info@twm-inc.com
- CARBONDALE OFFICE
206 WEST COLLEGE STREET
CARBONDALE, ILLINOIS 62901
TEL (618) 549-8844
FAX (618) 549-8450
info@twm-inc.com
- EDWARDSVILLE OFFICE
1015B CENTURY DRIVE
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
info@twm-inc.com
- ST. CHARLES OFFICE
400 NORTH 5TH ST., SUITE 101
ST. CHARLES, MISSOURI 63301
TEL (636) 724-8300
FAX (636) 724-8304
info@twm-inc.com
- WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
info@twm-inc.com

ILLINOIS PROFESSIONAL DESIGN FIRM	184-001220
PROFESSIONAL ENGINEERING CORP.	62-033370
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-005202
ILLINOIS PROF. LAND SURVEYING CORP.	048-000029
MISSOURI PROFESSIONAL ENGR. CORP.	NC 001528
MISSOURI LAND SURVEYING CORP.	NC 000346

PCC AND HMA PAVEMENT											
STATION	TO	STATION	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SUB-BASE GRANULAR MATL., TYPE-A 4"	PROCESSING MODIFIED SOIL 12"	LIME	PAVEMENT REMOVAL	AGGREGATE BASE CRSE TYPE A 6"	BIT. MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	INCIDENTAL HMA SURFACING
			SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD	GAL	TON	TON
12+42.92	RT	TO 29+19.36	1560.37	2105.67	2105.67	40.56					
23+76.49	RT	TO 25+01.07	239.00	276.10	276.10	5.32	220.62				
27+01.33	LT	TO 30+83.75	285.58	386.54	386.54	7.44					
28+32.38	RT	TO 29+00.64	88.19	114.94	114.94	2.21	81.19				
29+80.47	LT	TO 30+38.83					12.96	12.96	4.86	0.03	4.35
30+01.85	RT	TO 33+40.90	230.03	327.97	327.97	6.32					
30+78.02	LT	TO 30+85.67					4.26	4.26	1.60	0.01	1.43
32+44.02	LT	TO 33+08.24					14.30	14.27	5.35	0.04	4.80
TOTAL			2403	3211	3211	62	333	31	12	0.08	11

CURB, GUTTER, & SIDEWALK SCHEDULE									
STATION	TO	STATION	CURB REMOVAL	COMB. CONC. CURB & GUTTER REMOVAL	SIDEWALK REMOVAL	CONCRETE CURB, TYPE B	COMB. CONC. CURB & GUTTER TYPE B6.24	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	DETECTABLE WARNINGS
			FEET	FEET	SQ FT	FEET	FEET	SQ FT	SQ FT
12+42.96	RT	TO 24+09.62		1,188.38			1,183.41		
18+43.64	LT	TO 19+16.39		28.31			28.31		
18+43.64	LT	TO 26+36.85						3,691.77	46.00
23+66.68	RT	TO 24+09.91			307.39			315.64	12.00
23+93.55	LT	TO 24+01.55		7.98			7.98		
24+60.41	RT	TO 28+54.48		432.51			422.35		
24+78.42	RT	TO 28+95.00						1,864.34	30.00
26+24.14	LT	TO 26+42.94		22.65			22.65		
26+84.87	LT	TO 29+38.58		282.61			268.42		
26+88.22	LT	TO 29+30.51			1121.43			1,170.96	20.00
28+78.62	RT	TO 29+19.23		59.83			55.15		
29+68.64	LT	TO 30+94.68		157.22			146.18		
29+76.71	LT	TO 30+86.80						603.51	20.00
29+80.84	LT	TO 30+39.35	58.63			58.67			
30+01.91	RT	TO 32+43.42		272.80			258.40		
30+78.22	LT	TO 30+85.87				7.66			
31+31.71	LT	TO 31+63.44		41.90			41.90		
31+42.59	LT	TO 33+40.30						985.58	30.00
32+43.97	LT	TO 33+08.15	64.18			64.20			
32+71.15	RT	TO 33+40.90		94.02			86.85		
33+00.04	LT	TO 33+10.71		19.98			19.98		
33+24.99	LT	TO 33+37.13		21.94			22.33		
TOTAL			123	2,630	1,429	131	2,564	8,632	158

ENTRANCE SCHEDULE									
LOCATION (STATION)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	AGG BASE COURSE T-A, 6" (SQ YD)	AGG. FOR TEMPORARY ACCESS	INCIDENTAL HMA SURFACING (TON)	PCC DRIVEWAY PAVT.-6" (SQ YD)	PCC DRIVEWAY PAVT.-8" (SQ YD)	BITUMINOUS MATERIALS PRIME COAT (GAL)	AGG. (PRIME COAT) (TON)	
16+67.29 P.E	RT 111.84	63.64	10.67	7.13	31.98		23.87	0.16	
19+09.77 P.E.	RT 107.13	149.71	10.67	16.77	31.98		56.14	0.37	
23+52.90 P.E.	RT 98.85	88.93	10.67	9.96	37.42		33.35	0.22	
28+67.60	RT		25.78						
29+57.16 C.E.	LT 157.14		34.67			114.54			
31+17.89 C.E.	LT 153.03		24.89			137.06			
32+62.48 C.E.	RT 112.48		32.00			104.05			
33+17.97 C.E.	LT 28.03		15.11			28.03			
TOTAL		768	302	164	34	101	384	113	0.76

SCHEDULE OF QUANTITIES
FULLERTON ROAD WIDENING
VILLAGE OF SWANSEA
ST CLAIR COUNTY, ILLINOIS

REV.	DATE	DESCRIPTION
△		
△		
△		

PLAN STATUS: **FINAL**

ISSUED FOR REVIEW ISSUED FOR BIDDING
 ISSUED FOR CONSTR. RECORD DRAWING

DRAWN BY: JVV SHEET: **11**
DESIGNED BY: JVV
CHECKED BY: RSD OF 69 SHEETS
APPROVED BY: JVV PROJECT DESCRIPTION:
PROJECT NUMBER: T07050149

E:\050149 Fullerton Road\050149SSOB-QUANTITY SCHEDULES.dwg Plotted By: mlkzmlr