

FAU ROUTE	SECTION	COUNTY
9257	06-00011-02-RP	ST CLAIR
CONTRACT NO. 97448		ILLINOIS

THOUVENOT, WADE & MOERCHEN, INC.
ENGINEERS SURVEYORS PLANNERS



- CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
info@twm-inc.com
- CARBONDALE OFFICE
206 WEST COLLEGE STREET
CARBONDALE, ILLINOIS 62901
TEL (618) 549-8844
FAX (618) 549-8450
info@twm-inc.com
- EDWARDSVILLE OFFICE
1015B CENTURY DRIVE
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
info@twm-inc.com
- ST. CHARLES OFFICE
400 NORTH 5TH ST., SUITE 101
ST. CHARLES, MISSOURI 63301
TEL (636) 724-8300
FAX (636) 724-8304
info@twm-inc.com
- WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
info@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	184-001220
PROFESSIONAL ENGINEERING CORP.	62-035370
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-005202
ILLINOIS PROF. LAND SURVEYING CORP.	048-000029
MISSOURI PROFESSIONAL ENGR. CORP.	NC 001528
MISSOURI LAND SURVEYING CORP.	NC 000346

POLYUREA PAVEMENT MARKINGS											
STATION	DESCRIPTION	6" SOLID WHITE LINE	4" SKIP-DASH YELLOW LINE	4" SOLID YELLOW LINE	4" SOLID WHITE LINE	12" SOLID WHITE LINE	12" SOLID YELLOW LINE	24" SOLID WHITE LINE	LETTER & SYMBOLS	PAVEMENT MARKING REMOVAL	
		FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	SQ. FT.	SQ. FT.
FULLERTON ROAD											
12+42.76 L TO 12+42.76 R	33+40.90 L TO 33+40.90 R	LANE LINE		2097.57							
12+82.33 L TO 12+82.33 L	17+13.04 L TO 17+13.04 L	LANE LINE		430.58							
12+82.33 L TO 12+82.33 L	17+13.04 L TO 17+13.04 L	LANE LINE		430.73							
13+01.71 TO 13+01.71	17+03.56 TO 17+03.56	DIAGONALS					196.50				
17+13.04 TO 17+13.04	33+40.90 TO 33+40.90	4" SOLID YELLOW REMOVAL									
17+34.69 TO 17+34.69	33+40.90 TO 33+40.90	LEFT TURN ARROWS							234.00	1074.39	
17+34.86 LT TO 17+34.86 LT	32+74.87 LT TO 32+74.87 LT	10'-30' SKIP DASH	520.00								
17+34.86 RT TO 17+34.86 RT	32+74.87 RT TO 32+74.87 RT	10'-30' SKIP DASH	520.00								
23+36.20 TO 23+36.20	23+86.20 TO 23+86.20	DIAGONALS					70.70				
23+96.49 RT TO 23+96.49 RT	24+80.87 RT TO 24+80.87 RT	6" CROSSWALK REMOVAL									
23+97.50 TO 23+97.50	24+73.73 RT TO 24+73.73 RT	CROSSWALK						48.00		77.76	
24+03.40 RT TO 24+03.40 RT	24+30.08 TO 24+30.08	CROSSWALK						90.00			
24+30.08 RT TO 24+30.08 RT	24+62.36 RT TO 24+62.36 RT	CENTERLINE		37.50						3.30	
24+43.59 TO 24+43.59	24+62.36 RT TO 24+62.36 RT	STOP BAR									
24+66.10 LT TO 24+66.10 LT	25+41.10 LT TO 25+41.10 LT	LANE LINE			18.64	32.82					
26+34.89 LT TO 26+34.89 LT	26+89.64 LT TO 26+89.64 LT	LANE LINE			75.00						
26+41.70 LT TO 26+41.70 LT	26+84.72 LT TO 26+84.72 LT	CROSSWALK	54.79								
29+28.13 LT TO 29+28.13 LT	29+79.08 LT TO 29+79.08 LT	CROSSWALK	43.06								
29+34.10 LT TO 29+34.10 LT	29+73.04 LT TO 29+73.04 LT	CROSSWALK	50.95								
30+83.33 LT TO 30+83.33 LT	31+46.23 LT TO 31+46.23 LT	CROSSWALK	38.94								
30+89.90 LT TO 30+89.90 LT	31+39.08 LT TO 31+39.08 LT	CROSSWALK	62.54								
30+89.90 LT TO 30+89.90 LT	31+39.08 LT TO 31+39.08 LT	CROSSWALK	48.94								
32+96.14 LT TO 32+96.14 LT	33+40.90 LT TO 33+40.90 LT	LANE LINE		44.76							
33+09.14 LT TO 33+09.14 LT	33+25.50 LT TO 33+25.50 LT	CROSSWALK	16.37								
33+11.69 LT TO 33+11.69 LT	33+23.10 LT TO 33+23.10 LT	CROSSWALK	11.41								
TOTAL			327	1040	5095	94	33	267	138	234	1155

SIGNAGE SCHEDULE						
LOCATION (STATION)	OFFSET (FEET)	SIGN TYPE	DESCRIPTION	SIZE	SIGN PANEL-TYPE 1 (SQ. FT)	WOOD SIGN SUPPORT (FOOT)
17+25.01	24.08' RT	R3-9b	"CENTER LANE BI-DIRECTIONAL"	24" x 36"	6.00	13
18+64.50	22.94' RT	W14-2	"NO OUTLET"	24" x 24"	4.00	13
19+48.37	29.26' LT	R3-9b	"CENTER LANE BI-DIRECTIONAL"	24" x 36"	6.00	13
21+35.40	24.08' RT	R3-9b	"CENTER LANE BI-DIRECTIONAL"	24" x 36"	6.00	13
22+44.34	23.58' RT	W11-2	"PEDESTRIAN CROSSING"	30" x 30"	6.25	13
22+44.34	23.58' RT	W16-9P	"AHEAD"	24" x 12"	2.00	-
23+33.74	30.76' LT	R3-9b	"CENTER LANE BI-DIRECTIONAL"	24" x 36"	6.00	13
23+90.11	27.80' RT	W11-2	"PEDESTRIAN CROSSING"	30" x 30"	6.25	-
23+90.11	27.80' RT	W16-7P	DIAGONAL ARROW	24" x 12"	2.00	-
24+01.58	29.79' LT	W11-2	"PEDESTRIAN CROSSING"	30" x 30"	6.25	-
24+01.58	29.79' LT	W16-7P	DIAGONAL ARROW	24" x 12"	2.00	-
24+68.86	42.22' RT	W4-4P	"CROSS TRAFFIC DOES NOT STOP"	24" x 12"	2.00	-
25+50.94	31.17' LT	W11-2	"PEDESTRIAN CROSSING"	30" x 30"	6.25	13
25+50.94	31.17' LT	W16-9P	"AHEAD"	24" x 12"	2.00	-
26+02.39	31.08' RT	R3-9b	"CENTER LANE BI-DIRECTIONAL"	24" x 36"	6.00	13
28+12.62	31.08' LT	R3-9b	"CENTER LANE BI-DIRECTIONAL"	24" x 36"	6.00	13
30+02.22	24.32' RT	R3-9b	"CENTER LANE BI-DIRECTIONAL"	24" x 36"	6.00	13
32+16.33	28.91' LT	R3-9b	"CENTER LANE BI-DIRECTIONAL"	24" x 36"	6.00	13
TOTAL					87	143

SCHEDULE OF QUANTITIES

FULLERTON ROAD WIDENING VILLAGE OF SWANSEA ST CLAIR COUNTY, ILLINOIS

REV	DATE	DESCRIPTION
△		
△		
△		

PLAN STATUS:

FINAL

ISSUED FOR REVIEW ISSUED FOR BIDDING
 ISSUED FOR CONSTR. RECORD DRAWING

DRAWN BY: JJV SHEET: **12**
DESIGNED BY: JJV OF 69 SHEETS
CHECKED BY: RSD
APPROVED BY: JJV PROJECT DESCRIPTION
PROJECT NUMBER: T07050149