

STANDARDS

000001-08	STANDARDS SYMBOLS, ABBREVIATIONS, AND PATTERNS
630301-09	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631011-10	TRAFFIC BARRIER TERMINAL, TYPE 2
631031-17	TRAFFIC BARRIER TERMINAL, TYPE 6
701001-02	OFF ROADS OPERATIONS, 2L,2W, MORE THAN 15' AWAY FROM PAVEMENT EDGE
701006-05	OFF ROADS OPERATIONS, 2L,2W, 15'-24" FROM PAVEMENT EDGE
701011-04	OFF ROADS MOVING OPERATIONS 2L,2W DAY ONLY
701301-04	LANE CLOSURE 2L,2W, SHORT TERM OPERATIONS
701306-04	LANE CLOSURE 2L,2W, SHORT TERM OPERATIONS, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701311-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS -DAY ONLY
701316-13	LANE CLOSURE, 2L,2W, BRIDGE REPAIR FOR SPEEDS ≥ 45 MPH
701901-08	TRAFFIC CONTROL DEVICES
725001-01	OBJECT AND TERMINAL MARKERS
780001-05	TYPICAL PAVEMENT MARKINGS
781001-04	TYPICAL APPLICATIONS FOR RAISED REFLECTIVE PAVEMENT MARKERS
782006-01	GUARDRAIL AND BARRIER WALL REFLECTOR MOUNTING DETAILS
001006	DECIMAL OF AN INCH AND OF A FOOT
630001-12	STEEL PLATE BEAM GUARDRAIL

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STANDARDS, GENERAL NOTES AND COMMITMENTS
3-4	SUMMARY OF QUANTITIES
5-6	SCHEDULE OF QUANTITIES
7	075-0075 PLAN SHEET
8	075-0045 PLAN SHEET
9	075-0075 STAGING TYPICALS
10-11	075-0075 STAGING SHEETS
12-15	075-0075 STRUCTURE PLANS
16	075-0045 STAGING TYPICALS
17-18	075-0045 STAGING SHEETS
19-23	075-0045 STRUCTURE PLANS
24	BUTT JOINT DETAIL
25	MAX-WIDTH SIGN DETAIL

GENERAL NOTES

1 THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE

LOCATIONS	TL 96	TL 96
MIXTURE USE(S)	HMA SURFACE COURSE	PATCHING
AC/PG	PG 64-22	PG 64-22
DESIGN AIR Voids	4.0% @ N DESIGN - 5.0	4.0% @ N DESIGN - 5.0
MIXTURE COMPOSITION (GRADATION MIXTURE)	IL 9.5	IL 19.0
FRICTION AGGREGATE	MIX C	N/A
QUALITY MANAGEMENT	QC/QA	QC/QA
SUBLOT SIZE	N/A	N/A



- 2 AREAS OF DECK REPAIRS SHOWN ARE ESTIMATED. THE ENGINEER SHALL SHOW ACTUAL LOCATIONS OF DECK REPAIRS ON AS-BUILT PLANS.
- 3 ANY FULL DEPTH PATCHES THAT ARE DISCOVERED SHALL BE COVERED WHEN WORKERS AREN'T PRESENT.

COMMITMENTS

NONE

RATE TABLE

THE FOLLOWING RATES OF APPLICATION HAVE BEEN ASSUMED IN CALCULATING PLAN QUANTITIES.

0.025 LBS/SQ FT (HMA LIFTS)
BITUMINOUS MATERIALS (TACK COAT): 0.05 LBS/SQ FT (MILLING)
HMA SURFACE MIX "C": 0.056 TONS/SQ YD
AGGREGATE SHOULDERS: 1.60 TONS/CU YD

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DISTRICT 6**

EXAMINED October 20 2021
[Signature]
ENGINEER OF OPERATIONS

EXAMINED September 27 2021
[Signature]
ENGINEER OF PROJECT IMPLEMENTATION

EXAMINED October 14 2021
[Signature]
ENGINEER OF PROGRAM DEVELOPMENT

⚠️ REVISED 1-3-2021

REV. - MS

MODEL: D:\draft FILE: Main.dwg W:\dot\paw\benefit\com\pwwid\Documents\DOT\off\as\distrc\6\Projects\0672M27\CADD\Bates\CAD\sheet\0672M27-shc-gemote.dgn

USER NAME = coxjw	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/24/2021	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**GENERAL NOTES, STANDARDS, AND
INDEX OF SHEETS FAP 304 (IL 96)**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	(3,4)BDR	PIKE	25	2
CONTRACT NO. 72M27				
ILLINOIS FED. AID PROJECT				