



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 7, 2022

SUBJECT: Route FAS 61 (McConnell Road)
Section 19-00187-00-BR
Stephenson County
Contract No. 85717
Item 085
January 21, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Index to the Special Provisions.**
- 2. Revised page 4 of the Special Provisions.**
- 3. Revised sheet 6 of the Plans.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

Index to Special Provisions

Contents	Page
DESCRIPTION OF WORK	1
REMOVAL OF UNCLASSIFIED MATERIALS	1
PREPARATION OF ROADWAY BASE	1
STONE RIPRAP CL A4	1
TRAFFIC CONTROL PLAN	1-3
UTILITIES	3
TREE AND BRUSH REMOVAL	4
SAW CUTTING PAVEMENT	4
BRIDGE SCUPPERS	4
CORPS OF ENGINEERS 404 PERMIT	5-52
BORING LOGS	53-55
LR 107-4 INSURANCE	56
LR 702 CONSTRUCTION AND MAINTENANCE SIGNS	57
LR 1030 GROWTH CURVE	58-59

Stephenson County

Stephenson

19-00187-00-BR

TREE AND BRUSH REMOVAL:

This work will include removal and offsite disposal of trees and brush that are located within the work area of the project. Removal and disposal will be considered incidental to EARTH EXCAVATION and no additional payment will be made. Final limits of tree and brush removal will be approved by the Engineer.

Clearing of all shrubs, brush, debris, etc. within the project limits between the existing and temporary right-of-way lines, which are not called out on the plans, shall be accomplished in accordance with Section 201 of the Standard Specifications.

Basis of Payment: Clearing shall not be measured for payment, but shall be considered incidental to the contract.

SAW CUTTING PAVEMENT:

CH 19 shall be saw cut full depth at the ends of the improvements to provide a joint for the Hot-Mix Asphalt Pavement.

The work will not be paid for separately, but shall be considered as included in the contract unit price TON for HOT-MIX ASPHALT BINDER COURSE IL-19.0 N50" and no additional compensation will be allowed.

BRIDGE SCUPPERS (9" X 9.5" GRATE):

The work will not be paid for separately, but shall be considered as included in the contract unit price CU. YD. for "CONCRETE BOX CULVERTS" and no additional compensation will be allowed.

Revised 1/7/2022