

**SUMMARY OF QUANTITIES (CONTINUED)**

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 80% FEDERAL 20% LOCAL 0003	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS - IL RTE 31 80% FEDERAL 20% LOCAL 0021	SIGNALS - GREEN ST 80% FEDERAL 20% LOCAL 0021	SIGNALS - INTERCONNECT 80% FEDERAL 20% LOCAL 0021	LIGHTING 80% FEDERAL 20% LOCAL 0021	LOCAL 0% FEDERAL 100% LOCAL 0043
X7040125	PINNING TEMPORARY CONCRETE BARRIER	EACH	2,718	2,718						
X7280105	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	FOOT	1,500	1,500						
X7830060	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	1,475	1,475						
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	18,925	18,925						
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	6,530	6,530						
X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	95	95						
X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	1,360	1,360						
X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	460	460						
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2			1	1			
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	2			1	1			
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	2,550					2,550		
XX004907	GATE VALVE 12" WITH VAULT, 5' DIAMETER	EACH	1							1
XX005230	VIDEO DETECTION SYSTEM COMPLETE INTERSECTION	L SUM	1				1			
XX006852	EXPLORATION TRENCH, SPECIAL	CU YD	100	100						
XX008698	WET REFLECTIVE PREFORMED PLASTIC MARKINGS-LETTERS AND SYMBOLS	SQ FT	1,475							1,475
XX008699	WET REFLECTIVE PREFORMED PLASTIC MARKINGS, 4 INCH	FOOT	18,925							18,925
XX008700	WET REFLECTIVE PREFORMED PLASTIC MARKINGS, 6 INCH	FOOT	6,530							6,530
XX008701	WET REFLECTIVE PREFORMED PLASTIC MARKINGS, 8 INCH	FOOT	95							95
XX008702	WET REFLECTIVE PREFORMED PLASTIC MARKINGS, 12 INCH	FOOT	1,360							1,360
XX008703	WET REFLECTIVE PREFORMED PLASTIC MARKINGS, 24 INCH	FOOT	460							460
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	50	50						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	20	20						
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	2	2						
Z0022800	FENCE REMOVAL	FOOT	71	71						
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	870	870						
Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1					1		
Z0034105	MATERIAL TRANSFER DEVICE	TON	7.619							7.619
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1						
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	930	930						
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	231	231						
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	633	633						
Z0062456	TEMPORARY PAVEMENT	SQ YD	10,104	10,104						
Z0066400	STABILIZED DRIVEWAYS 6"	SQ YD	758	758						
Z0066600	STABILIZED DRIVEWAYS 8"	SQ YD	2,403	2,403						
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2			1	1			
X Z0076600	TRAINEES	HOUR	1,500							
X Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1,500							

- SPECIALTY ITEM
- X CONSTRUCTION TYPE CODE 0042

COMPANY NAME: HRGreen  
 PROJECT CONTACT: HRGreen.com  
 DATE PLOTTED: 12/4/2014 9:42:06 AM  
 FILE NAME: 090071-sum.dgn  
 PLOT DRIVER: pdfplot  
 PEN TABLE: standard-trans.tbl



USER NAME = tye1son	DESIGNED - JPA	REVISED - $\Delta$ 1/16/15
FILE NAME = 090071-sum.dgn	DRAWN - SVJ	REVISED -
PLOT SCALE = N.T.S.	CHECKED - JLP	REVISED -
PLOT DATE = 12/4/2014	DATE - 12/5/14	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
CHARLES J. MILLER ROAD ROADWAY IMPROVEMENTS**

SCALE: N.T.S. SHEET NO. 7 OF 7 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3860	09-00372-01-PW	MCHENRY	358	10
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63892	