

CONTRACT 60G52
TEMPORARY INFORMATION SIGNING - STAGE 1

STATION	LEGEND/DESCRIPTION	PANEL		PANEL
		COVER DIMENSIONS		COVER AREA
		WIDTH (FT)	HEIGHT (FT)	(SQ FT)
468+05	TRAFFIC	1.5	7.2	10.8
482+30	TRAFFIC	1.5	7.2	10.8
505+00	ALL LANES	1.8	12.5	22.9
522+50	ALL LANES	1.8	12.5	22.9
546+40	ALL LANES	1.8	12.5	22.9
522+50	LEFT 1/4 MILE	1.8	12.5	22.9
546+40	LEFT 3/4 MILE	1.8	12.5	22.9
600+00	COVER	12.0	17.5	210.0
590+80	COVER	8.0	14.0	112.0
NA	2010 REPAIR & RESURFACING	9.0	17.0	153.0
482+30	COVER	8.0	14.0	112.0
468+05	COVER	10.0	17.0	170.0
482+30	COVER	10.0	17.0	170.0
496+20	COVER	2.5	3.3	8.3
505+00	COVER	2.0	2.0	4.0
505+00	ARROW	2.0	2.0	4.0
TOTAL				1079.4

CONTRACT 60G52
TEMPORARY INFORMATION SIGNING - STAGE 2

STATION	LEGEND/DESCRIPTION	PANEL		PANEL
		COVER DIMENSIONS		COVER AREA
		WIDTH (FT)	HEIGHT (FT)	(SQ FT)
468+05	TRAFFIC	1.5	7.2	10.8
482+30	TRAFFIC	1.5	7.2	10.8
522+50	LEFT 1/4 MILE	1.8	12.5	22.9
546+40	LEFT 3/4 MILE	1.8	12.5	22.9
600+00	COVER	12.0	17.5	210.0
590+80	COVER	8.0	14.0	112.0
482+30	COVER	8.0	14.0	112.0
468+05	COVER	10.0	17.0	170.0
482+20	COVER	10.0	17.0	170.0
505+00	COVER	2.0	2.0	4.0
522+50	COVER	2.0	2.0	4.0
522+50	ARROW	2.0	2.0	4.0
TOTAL				853.3

CONTRACT 60G52
TEMPORARY PAVEMENT MARKING AND TEMPORARY IMPACT ATTENUATOR SCHEDULE

STAGE	WET REFLECTIVE TEMPORARY TAPE - LETTERS AND SYMBOLS	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	TEMPORARY PAVEMENT MARKING - LINE 6"	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	EPOXY PAVEMENT MARKING - LINE 4 INCH	EPOXY PAVEMENT MARKING - LINE 8 INCH	EPOXY PAVEMENT MARKING - LINE 5 INCH	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	(SQ FT)	(FOOT)	(FOOT)		(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)
1		34,262	2,220	5,641	14,086	1,684	10,258					15	2		
2	109	40,880	8,228	5,871	8,703	381	4,171							2	5
RESURFACING		7,624	10,510		1,334	1,150		1,000	286,562	31,812	58,408				
TOTAL	109	82,766	20,958	11,512	24,122	3,215	14,429	1,000	286,562	31,812	58,408	15	2	2	5

FILE NAME =	DESIGNED - AJP	REVISED -
...prpIn_ABC.C2_sch_03.cgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 1/25/2010	DATE - 1/25/10	REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3435, ETC., 3838)RS-5	COOK	264	20
CONTRACT NO. 60G52			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	