


WESTBOUND SIGN SCHEDULE			EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1	REMOVE SIGN PANEL-TYPE 2	REMOVE SIGN PANEL-TYPE 3	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL ASSEMBLY - TYPE B	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	SIGN PANEL TYPE 3	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT	REMOVAL OF LIGHTING UNIT, NO SALVAGE
SIGN NO.	STATION	LEGEND/DESCRIPTION	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	(SQ FT)	(SQ FT)	(SQ FT)	EACH	EACH	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(EACH)
WB-CL-59	489+90	EXIT 15B - I 294 NORTH TOLLWAY - MILWAUKEE - EXIT ONLY	11.0	8.0	14.0	12.5			88.0					175.0			1.0
WB-WP-60	503+00	EXIT 15A	7.5	5.0	7.0	5.0					1.0			35.0	36.0		
WB-TR-61	505+00	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - EXIT ONLY	25.0	10.5	25.0	11.5			262.5					287.5			1.0
WB-TR-62	505+00	EXIT 15B - I 290 WEST I-294 NORTH TOLLWAY - ROCKFORD MILWAUKEE	25.0	10.5	25.0	11.5			262.5					287.5			1.0
WB-WM-62A*	509+00	WOLF RD	1.8	8.7	1.8	8.7		15.2				15.2					
WB-TR-63	522+50	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - EXIT ONLY	25.0	10.5	25.0	11.5			262.5					287.5			1.0
WB-TR-64	522+50	EXIT 15B - I 290 WEST I-294 NORTH TOLLWAY - ROCKFORD MILWAUKEE	25.0	10.5	25.0	11.5			262.5					287.5			1.0
WB-PM-64A	522+50	R2-1 (55 MPH)	4.0	5.0	4.0	5.0		20.0				20.0					
WB-GM-65	530+00	O'HARE - USE I 294 NORTH - EXIT 15B	16.0	10.0	16.0	10.5			160.0					168.0			
WB-WP-66	535+00	EXIT 16	6.0	5.0	6.0	5.0					1.0			30.0	36.0		
WB-WM-66A	540+81	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0				20.0					
WB-TR-67	541+20	LEFT EXIT 15A - IL 38 ROOSEVELT RD - LEFT 3/4 MILE	23.5	9.5	23.5	9.5			223.3					223.3			1.0
WB-TR-68	541+20	EXIT 16 - WOLF RD	14.5	8.5	14.5	8.5			123.3					123.3			1.0
WB-TR-69	546+40	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - EXIT ONLY	24.0	12.0	25.0	12.0			288.0					300.0			1.0
WB-TR-70	546+40	EXIT 15B - I 290 WEST I-294 NORTH TOLLWAY - ROCKFORD MILWAUKEE	24.0	12.0	25.0	12.0			288.0					300.0			1.0
WB-WP-70A	558+77	W4-1R	4.0	4.0	4.0	4.0					1.0		16.0		18.0		
WB-BM-71	565+70	EXIT 16 - WOLF RD - 1/2 MILE	11.0	8.0	11.5	8.0			88.0					92.0			1.0
WB-BM-71A*	565+70	US RT 12-20-45 - MANNHEIM RD	9.4	2.5	9.4	2.5		23.6				23.6					
WB-WP-71B	568+32	W4-3R	4.0	4.0	4.0	4.0		16.0				16.0			18.0		
WB-PM-71C	572+00	END - TRUCK - LANE - RESTRICTIONS	4.0	5.0	4.0	5.0		20.0				20.0					
WB-WP-72	576+50	EXIT 17	6.0	5.0	6.0	5.0					1.0		30.0	36.0			
WB-BM-72A*	579+21	WESTCHESTER BLVD	10.8	1.5	10.8	1.5		16.2				16.2					
WB-TS-72B	580+08	W13-3 (30 MPH)	3.0	4.0	4.0	5.0					1.0		20.0		18.0		
WB-TR-73	582+85	LEFT EXIT 15A - I 88 WEST TOLLWAY I-294 SOUTH TOLLWAY - AURORA INDIANA - LEFT 1 1/2 MILES	23.5	12.5	24.0	12.5			293.8					300.0			1.0

\*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -	 <b>LIN ENGINEERING, LTD.</b> Consulting Engineers <small>Channah, Illinois Westmont, Illinois</small>	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL*	DRAWN - SEW	REVISED -			290	(3435, ETC., 3838)RS-5	COOK	264	22			
USER NAME = #USER*	CHECKED - FML	REVISED -			CONTRACT NO. 60G52							
PLOT DATE = #DATE*	DATE = 1/25/10	REVISED -			SCALE: N.T.S.	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		