SIGN DETAIL

1:75

WB-CL-59
STA. 489+90

FONT:
(1) ClearviewHwy-5-W
(2) ClearviewHwy-5-W-R

SIGN NUMBER	name
WIDTH x HGHT.	14'-0" x 12'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	18.3	73.1	45	36
ARDOWN	0	68	12	32	22

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																																	LENGTH	SERIES-SIZE
E	X	I	T	1	5	B																												ClearviewHwy-5-W
68.9	79.2	92.8	98.8	117.4	129.4	145.1																											87.5	12,15
N	O	R	T	H																														ClearviewHwy-5-W
75.3	92.5	107.9	119.8	132																													65.9	15,12
T	O	L	L	W	A	Y																												ClearviewHwy-5-W-R
75.3	84.4	96.7	105.1	112.6	127.1	137.4																											70.9	10
M	i	l	w	a	u	k	e	e																										ClearviewHwy-5-W-R
18.3	37.8	46.3	53.4	74.3	90.2	106.2	120	135.6																									129.1	16/13

FILE NAME =	DESIGNED - SEW	REVISED -	LIN ENGINEERING,LTD. Consulting Engineers Chatham, Illinois Westmont, Illinois
$FILEL$	DRAWN - SEW	REVISED -	
USER NAME = $USER$	CHECKED - FML	REVISED -	
PLOT DATE = $DATE$	DATE - 1/25/10	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 19 OF 43 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3435, ETC., 3838)RS-5	COOK	264	174
		CONTRACT NO. 60G52		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		