SIGN DETAIL
1:75

WB-GM-83
STA. 646+20

SIGN NUMBER	name	
WIDTH x HGHT.	14'-0" x 10'-0"	
BORDER WIDTH	2"	
CORNER RADIUS	12"	
MOUNTING	Ground	
BACKGROUND	TYPE:	Reflective
	COLOR:	Green
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	White/White

SYMBOL	ROT	X	Y	WID	HT

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)							LENGTH	SERIES/SIZE
E	X	I	T	1	8	B		ClearviewHwy-5-W
61.7	72	85.6	91.5	110.2	122.3	138.6	88.3	12,15
N	O	R	T	H				ClearviewHwy-5-W
52.3	69.5	84.9	96.8	109			65.9	15,12
2	5	t	h		A	v	e	ClearviewHwy-5-W-R
28.8	43.8	57.8	69.6	80.7	96.2	112.7	127.4	110.4	1613
½	M	I	L	E				ClearviewHwy-5-W
51.1	82.4	95.6	101.5	110.5				65.8	15,10

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 1/25/10	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 38 OF 43 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3435, ETC., 3838)RS-5	COOK	264	193
		CONTRACT NO. 60G52		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		