

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

1. Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.
2. Reinforcement bars designated (E) shall be epoxy coated.
3. Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
4. Concrete Sealer shall be applied to the bridge deck, parapets, approach slabs, abutment seats and abutment backwalls. All surfaces to be sealed shall be cleaned thoroughly prior to sealer application. Cost included in Concrete Sealer.
5. The existing structural steel coating contains lead. The Contractor shall take appropriate precautions to deal with the presence of lead on this project.
6. Stage construction shall be utilized to maintain traffic during construction.

INDEX OF SHEETS

1. General Plan and Elevation
2. General Notes, Bill of Material and Index of Sheets
3. Stage Construction Details
4. Bridge Deck, Approach Slab and Parapet Repairs

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Protective Shield	Sq. Yd.	127		127
Concrete Sealer	Sq. Ft.	26,094	1,280	27,374
Silicone Joint Sealer	Foot	237.0		237.0
Structural Repair of Concrete (Depth Greater Than 5 Inches)	Sq. Ft.	10		10
Approach Slab Repair (Partial Depth)	Sq. Yd.	20.6		20.6
Deck Slab Repair (Partial)	Sq. Yd.	38.3		38.3
Cleaning and Painting Exposed Rebar (Special)	Sq. Ft.	10		10
Clean & Reseal Relief Joint	Foot	144.0		144.0

DESIGNED -	DMS
CHECKED -	EFS
DRAWN -	RMG
CHECKED -	KWS

**GENERAL NOTES, BILL OF MATERIAL
AND INDEX OF SHEETS
STRUCTURE NO. 016-0086**

benesch

alfred benesch & company
Engineers • Surveyors • Planners
205 North Michigan Avenue, Suite 2400
Chicago, Illinois 60601
312-565-0450 Job No. 10050

SHEET NO. 2 4 SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	290	(3435, ETC., 3838)RS-5	COOK	264	211
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT		
				CONTRACT NO. 60G52	