

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY <i>100% STATE</i>	0005 STATE	0031 LANDSCAPING
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	4	4	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	79		79
25000210	SEEDING, CLASS 2A	ACRE	0.02		0.02
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1		1
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1		1
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1		1
25100630	EROSION CONTROL BLANKET	SQ YD	79		79
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24	
40600300	AGGREGATE (PRIME COAT)	TON	118	118	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	44	44	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	357	357	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,486	2,486	
42001300	PROTECTIVE COAT	SQ YD	33	33	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	29,591	29,591	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	280	280	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	120	120	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	149	149	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	589	589	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	150	150	
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4,205	4,205	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	42,046	42,046	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	582	582	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	132	132	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	366	366	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,402	1,402	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21,023	21,023	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	291	291	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	66	66	
* 78000850	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	183	183	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	151	151	
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	10	10	
* 78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	75	75	
Z0004562	COMBINATION CONCRETE CURB ^{AND} GUTTER, REMOVAL ^{AND} REPLACEMENT	FOOT	100	100	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51	51	
X2503100	MOWING	UNIT	14		14
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,243	1,243	
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	210	210	

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = .USER.	DESIGNED - AR/EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 113 - COAL CITY RD TO MAIN ST. SUMMARY OF QUANTITIES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL*	PLOT SCALE = 50,0000' / IN.	DRAWN - AR/EF	REVISED -					2320	113X-RS-4	WILL	13	3
	PLOT DATE = 10/14/2010	CHECKED - RS	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 60L59			
		DATE - 10-15-2010	REVISED -		ILLINOIS FED. AID PROJECT							