

GENERAL NOTES

1. THE STANDARDS AND REVISIONS LISTED APPLY TO THIS PROJECT.
2. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT INTERCHANGES, ENTRANCES, AND SIDE STREETS WHERE WORK IS BEING CONDUCTED AS DIRECTED BY THE RESIDENT ENGINEER. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE. THIS SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION. THESE SIGNS SHALL BE 48" X 48"
3. ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.
4. IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16, THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 107.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
5. NO OVERNIGHT LANE CLOSURE WILL BE ALLOWED.
6. THE FOLLOWING PAIRS OF STRUCTURES SHALL BE STAGED AS ONE WORK ZONE AND WORK PERFORMED CONCURRENTLY ON EACH PAIR:

SN 060-0083 & SN 060-0158
 SN 060-0259 & SN 060-0260
 SN 060-0129 & SN 060-0130

NO COMMITMENTS

BRIDGE LOCATIONS								
STRUCTURE NO.	ROUTE	OVER	LOCATION	NET LENGTH	ADT 2011	ADT 2031	% SU	% MU
SN 060-0004	FAI 55 FR# 1836	UNION PACIFIC RR	NORTH OF NEW DOUGLAS ROAD	204.03	125	150	3.0	1.0
SN 060-0073	IL 140	FAI 55	IN HAMEL	209.65	8000	9800	5.8	2.9
SN 060-0083	IL 143	CAHOKIA CREEK	NORTHWEST OF IL 159	194.39	10100	12300	2.5	1.3
SN 060-0084	IL 159/IL 143	N&W RR	0.1 MILES NORTHWEST OF EDWARDSVILLE	149.23	13000	15900	2.6	0.8
SN 060-0091	IL 140	WOOD RIVER CREEK	0.3 MILES EAST OF IL 3/111	172.44	23500	28700	2.8	1.6
SN 060-0118	IL 3 (HOMER ADAMS PARKWAY)	US 67	1 MILE EAST OF JCT 111	468.79	20000	24400	1.5	1.1
SN 060-0121	IL 111	CAHOKIA DIVERSION CANAL	3 MILES NORTH OF JCT 270 & 111	383.58	5300	6500	4.8	5.8
SN 060-0122	IL 111	UNION PACIFIC RR	2 MILES NORTH OF JCT I-270 & IL 111	314.79	5400	6600	5.7	4.7
SN 060-0123	IL 111	POAG ROAD & N&W RR	1.25 MILES NORTH OF JCT I-270 & IL 111	365.39	5400	6600	5.7	4.7
SN 060-0129	IL 159	CAHOKIA CREEK	0.25 MILES NORTH OF EDWARDSVILLE	232.57	7650	9300	2.3	1.2
SN 060-0130	IL 159	MOONEY CREEK	NORTH OF IL 143	168.78	7650	9300	2.3	1.2
SN 060-0148	IL 143	FAI 55	2 MILES EAST OF EDWARDSVILLE	190.81	6600	8100	3.5	1.4
SN 060-0158	IL 143	OLD CAHOKIA CREEK	0.25 MILES WEST OF JCT IL 143/159	115.21	10100	12300	2.5	1.3
SN 060-0213	IL 3	IL 140	0.4 MILES WEST OF FOSTERBERG ROAD	231.00	23500	28700	2.8	1.6
SN 060-0254	US 67	ALBY STREET	1.42 MILES SOUTH OF BELTLINE	135.82	12300	15000	3.1	4.1
SN 060-0256	IL 143	NS&SPC RR	IN ALTON EAST OF CLARK	195.32	14800	18100	3.1	2.6
SN 060-0258	IL 140	STREAM	0.2 MILES EAST OF JCT IL 140/4	63.65	2700	3300	5.8	3.1
SN 060-0259	IL 140	SILVER CREEK OVERFLOW	0.4 MILES EAST OF IL 140/4	120.69	2700	3300	5.8	3.1
SN 060-0260	IL 140	SILVER CREEK	0.5 MILES EAST OF IL 140/4	160.83	2700	3300	5.8	3.1
SN 060-0268	IL 3 SB	WOOD RIVER CREEK	WEST CITY LIMITS OF EAST ALTON	233.52	14300	17500	3.9	2.0
SN 060-0271	IL 159	CONRAIL	3 MILES NORTH OF IL 143	182.75	6800	8300	2.6	1.3
SN 060-0315	IL 3 NB	CAHOKIA DIVERSION CANAL	2.5 MILES NORTH OF I-270	337.17	8800	10700	4.1	5.8
SN 060-0316	IL 3 SB	CAHOKIA DIVERSION CANAL	2.5 MILES NORTH OF I-270	337.21	9100	11100	5.6	6.7

CB Coombe-Bloxdorf P.C.
 -CIVIL ENGINEERS-
 -STRUCTURAL ENGINEERS-
 -LAND SURVEYORS-
 Design Firm License No. 184-002703

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	DIST 8 BRIDGE DECK 2011-4	MADISON	29	3
CONTRACT NO. 76E44				
ILLINOIS FED. AID PROJECT				

FILE NAME = ... \003_D876E44-shr-genote.dgn	USER NAME = MML...	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	SCALE:	SHEET NO. OF SHEETS STA. TO STA.
	PLOT SCALE = 50.0000' / IN.	DRAWN - MML	REVISED -				
	PLOT DATE = 11/29/2010	CHECKED - MCB	REVISED -				
CB PROJECT NO 09025-4		DATE - 11/4/2010	REVISED -				