

FILE PATH - p:\11382924-p\11382924\11382924.dwg  
 PROJECT - TRANSPORTATION  
 CONTRACT NO. 60W29  
 COUNTY COOK  
 SECTION 2013-011R  
 SHEET NO. 9

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	ROADWAY	BRIDGE	LIGHTING	OTHER	
				90% FED		90% FED	90% FED	90% FED	
				10% STATE	100% STATE	10% STATE	10% STATE	10% STATE	
				0004	0004	0011	0021	0044	
URBAN	URBAN	016-1708	URBAN	URBAN					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	125	125					
44000300	CURB REMOVAL	FOOT	50	50					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	774	774					
44000600	SIDEWALK REMOVAL	SQ FT	16,344	16,344					
44001980	CONCRETE BARRIER REMOVAL	FOOT	507	507					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1			
50157300	PROTECTIVE SHIELD	SQ YD	1,394			1,394			
50200100	STRUCTURE EXCAVATION	CU YD	3368	75		3,293			
50300225	CONCRETE STRUCTURES	CU YD	1060.1	28.9		1031.2			
50300254	<b>RUBBED FINISH</b>	<b>SQ FT</b>	<b>4065</b>			<b>4065</b>			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	209.3			209.3			
50300285	FORM LINER TEXTURED SURFACE	SQ FT	1020			1020			
50300300	PROTECTIVE COAT	SQ YD	395			395			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1			
50500505	STUD SHEAR CONNECTORS	EACH	6,806			6,806			

\* DENOTES SPECIALTY ITEM

\*\* DENOTES NON-PARTICIPATING ITEM



DESIGNED - JLV  
 DRAWN - BAW  
 CHECKED - JMG  
 DATE - 10/30/2013

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET 4 OF 17 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	9
CONTRACT NO. 60W29			ILLINOIS FED. AID PROJECT	

Rev.