

FILE PATH = p:\388035\pmt\escomon\me\local\PAEC000\Documents\01_Americas\Transportation\60269938_Circle\Phase_1\1000_CAD\005_Roadway_Sheets\60W29_Contract\0160W29-sht-Pmk-Schedule.dgn

PAVEMENT MARKING SCHEDULE

LOCATION	STATION	TO	STATION	EPOXY PAVEMENT MARKING - LINE 4"	EPOXY PAVEMENT MARKING - LINE 5"	EPOXY PAVEMENT MARKING - LINE 8"	EPOXY PAVEMENT MARKING - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	PAVEMENT MARKING REMOVAL
				FOOT	FOOT	FOOT	FOOT	EACH	EACH	SQ FT
PEORIA STREET										
I-290 WB				1,034	584	1,017	53	8	8	1,313
I-290 EB				1,880	1,341	3,165	369	95	90	3,374
TOTALS				2,914	1,925	4,182	421	103	98	4,687



DI60W29-sht-Pmk-Schedule.dgn	DESIGNED - JDT	REVISED - 12/18/2013
USER NAME = BAWtor t	DRAWN - JTR	REVISED -
PLOT SCALE = 20.0000' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 12/19/2013	DATE - 10/30/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PAVEMENT MARKING PLAN
SCHEDULE**

SCALE: NONE SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-011R	COOK	356	96
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60W29	