

NOTES:

- 1. THE DIMENSIONS ARE SHOWN RELATIVE TO THE CENTER OF THE 12' LANE.
- 2. THE DASHED OUTLINE IN THE DETAIL SHOWS THE FUTURE PERMANENT SIGNS AFTER MAINLINE RECONSTRUCTION IS COMPLETE (TYPICAL). PEORIA STREET OVERHEAD SIGNS SHALL BE PLACED ON THE BRIDGE MOUNTS ERECTED IN CONTRACT 60W25.
- 3. THE BOTTOM OF SIGN PANEL ELEVATION SHOWN IN THE DETAILS SHALL BE MAINTAINED THROUGH STAGES 1A, 1B, AND POST-CONSTRUCTION.
- 4. THE RIGHT VERTICAL BRACKET SHALL BE INSTALLED IN CONTRACT 60W25 TO ACCOMMODATE SIGN EB-02-BM DURING STAGE IA AND POST-CONSTRUCTION. ANY ADJUSTMENTS TO THE BRACKETS DURING THIS CONTRACT SHALL BE INCLUDED IN THE COST OF THE SIGN PANEL AND PAID FOR AS SIGN PANEL TYPE-3. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.
- 5. RELOCATE THE PROPOSED DEMOUNTABLE DOWN ARROW OVER THE CENTER OF THE LANE ONCE TRAFFIC IS IN THE FINAL CONFIGURATION. SEE SHEET 107 FOR DETAILS.

SCALE: NONE



D160W29-sht-Sign-Det-05.dgn	DESIGNED - JDT	REVISED - 🛕 01/20/20
USER NAME = mnbaldwin	DRAWN - JTR	REVISED -
PLOT SCALE = 10.0000 ' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 1/21/2014	DATE - 10/30/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

.....

OVERHEAD SIGN STRUCTURES SIGN LAYOUT			F.A.I. RTE.			
			90/94/290	2		
SHEET 4A	OF 5	SHEETS	STA.	TO STA.		