

CODE NO	ITEM	UNIT	TOTAL QUANTITY
			CONSTRUCTION CODE 0005
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20
20700220	POROUS GRANULAR EMBANKMENT	CU YD	20
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	400
25000110	SEEDING, CLASS 1A	ACRE	0.18
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15
28000510	INLET FILTERS	EACH	25
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2830
40600300	AGGREGATE (PRIME COAT)	TON	43
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	793
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	150
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1387
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6126
42400800	DETECTABLE WARNINGS	SQ FT	242
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	14150
44000600	SIDEWALK REMOVAL	SQ FT	6126
44003100	MEDIAN REMOVAL	SQ FT	120
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	25
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	50
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	150
60107600	PIPE UNDERDRAINS 4"	FOOT	75
60255500	MANHOLES TO BE ADJUSTED	EACH	1

CODE NO	ITEM	UNIT	TOTAL QUANTITY
			CONSTRUCTION CODE 0005
60280100	INLETS TO BE ADJUSTED	EACH	9
60262700	INLETS TO BE RECONSTRUCTED	EACH	1
67100100	MOBILIZATION	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT TERM PAVEMENT MARKING	FOOT	500
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	150
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2500
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	534
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	200
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4412
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	727
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1350
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	293
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1060
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1086

\* INDICATES SPECIALTY ITEM