

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
			CONSTR. CODE FED / STATE 90% / 10% ROADWAY	GRUNDY	LIVINGSTON
			0021	0021	0021
			RURAL	RURAL	RURAL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	1128	564	564
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SO YD	81174	40,587	40,587
44000189	HOT-MIX ASPHALT SURFACE REMOVAL, 10"	SO YD	17866	8,933	8,933
40603082	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N50	TON	7004	3,502	3,502
40603415	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, FG, N50	TON	16638	8,319	8,319
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	120589		120,589
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	4	4
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	28	14	14
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	1	1
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	100	50	50
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	2	1	1
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	84764	42,382	42,382
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	L SUM	1	0.5	0.5
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	42	21	21

⚠

⚠ Rev. 2-18-14

Rev.