

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	M231	M232	M231
				ACM	ACRS	ACM
				CONSTRUCTION CODE		
				STA. 97+55.22 TO STA. 142+00.00 FAU 7152 FED-80% STATE-20% ROADWAY	STA. 142+00.00 TO STA. 417+19.15 FAS 1512 FED-80% STATE-20% ROADWAY	COTTONWOOD DR. STA. 101+00.00 S. N. 010-2039 FED-80% STATE-20% BOX CULVERT
				0004 URBAN	0004 RURAL	0011 URBAN
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	72,617.0	10,748.0	61,869.0	0.0
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	100.0	51.0	49.0	0.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	396.0	55.0	341.0	0.0
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	17.0	8.0	9.0	0.0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	16.0	8.0	8.0	0.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	396.0	55.0	341.0	0.0
* A2000192	TREE, ACER X FREEMANII AUTUMN FANTASY (AUTUMN FANTASY FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3.0	0.0	3.0	0.0
* A2004816	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	4.0	0.0	4.0	0.0
* A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	1.0	0.0	1.0	0.0
* A2008016	TREE, TILIA CORDATA (LITTLE LEAF LINDEN), 2" CALIPER, BALLED AND BURLAPPED	EACH	2.0	0.0	2.0	0.0
* B2001160	TREE, CERCIDIPHYLLUM JAPONICUM (KATSURA TREE), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	1.0	0.0	1.0	0.0
* B2001616	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	1.0	0.0	1.0	0.0
* B2010042	TREE, CHIONANTHUS VIRGINICUS (WHITE FRINGETREE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	1.0	0.0	1.0	0.0
* D2001924	EVERGREEN, PICEA GLAUCA DENSATA (BLACK HILLS SPRUCE), 2' HEIGHT, BALLED AND BURLAPPED	EACH	2.0	0.0	2.0	0.0
* D2003848	EVERGREEN, THUJA OCCIDENTALIS TECHN (TECHNY ARBORVITAE), 4' HEIGHT, BALLED AND BURLAPPED	EACH	4.0	0.0	4.0	0.0

15

* SPECIALTY ITEM

CONT'D NEXT SHEET

FILE NAME : c:\p\work\p\p\shere-jn\0120316\0570663-shc-300.dgn	USER NAME : shere-jn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE : 40.0000' / 1" =	CHECKED - DATE -	REVISED - REVISED -	SCALE: N/A		SHEET 9	OF 11 SHEETS	STA.	TO STA.	12X, 3RS-3 & 2RS-4	Champaign	551	15	
PLOT DATE : 18/18/2013	DATE -	REVISED - REVISED -							CONTRACT NO. 70663				
ILLINOIS FED. AID PROJECT													