

63200310 GUARDRAIL REMOVAL

STATION	IQ	STATION	FOOT
RURAL			
RT 396+68.89		RT 398+44.67	175.0
LT 397+57.95		LT 398+44.57	100.0
LT 400+92.96		RT 402+56.63	187.5
RT 400+93.78		LT 401+81.39	100.0
TOTAL =			562.5

XQ327171 SCARIFY EXISTING SURFACE

STATION	IQ	STATION	SQ YD	
URBAN				
COTTONWOOD DR	SOUTH	86+00.00	99+88.00	2850.9
COTTONWOOD DR	NORTH	100+12.00	108+50.00	1946.2
RURAL				
TR 1800 E		LT 194+82.68	195+69.34	163.0
TR 1800 E		RT 194+85.08	195+53.48	114.0
TR 1900 E		LT 250+24.21	251+27.02	442.4
TR 1900 E		RT 250+45.98	251+15.19	334.1
TR 1975 E		RT 290+61.91	291+25.00	128.5
TR 2000 E		LT 303+73.10	304+53.07	106.2
TR 2075 E		RT 343+60.24	344+14.19	89.1
TOTAL =			6,174.4	
USE =			6,175.0	

X4400196 HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL

STATION	PE	PE/MBIQ	MBIQ	CE	FE	SQ YD
URBAN						
LT 109+45.06	27.0					27.0
LT 110+00.00	31.0					31.0
LT 110+92.94	27.0					27.0
LT 111+95.55	29.4					29.4
LT 113+23.49	43.0					43.0
LT 114+30.37	33.0					33.0
RURAL						
LT 224+00.24		48.0				48.0
LT 224+93.97	44.5					44.5
LT 225+78.11	44.5					44.5
LT 227+29.83		55.7				55.7
LT 228+18.95		50.0				50.0
LT 229+21.06	35.5					35.5
LT 229+65.47	35.5					35.5
LT 231+18.13			36.0			36.0
LT 357+46.35			46.0			46.0
RT 356+04.59	181.5					181.5
LT 370+18.95			190.1			190.1
TOTAL =						957.7
USE =						958.0

5421D024 PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)

STATION	FOOT	CU YD
URBAN		
125+72.00	50.0	22.0
140+00.00	50.0	22.0
RURAL		
144+00.00	50.0	22.0
158+00.00	50.0	22.0
TOTAL =		200.0
		88.0

DESIGN NOTE: TEMPORARY PIPE CULVERTS SHALL BE PLACED PRIOR TO RAISING US 150 TO MAINTAIN DRAINAGE WHILE EXISTING A. R. CULVERTS ARE FILLED WITH CLSM. TEMPORARY CULVERTS SHALL BE REMOVED AFTER US 150 IS RAISED. COST OF REMOVAL SHALL BE INCLUDED WITH THE COST OF THE PRECAST BOX CULVERTS OF THE TYPE AND SIZE SPECIFIED IN THE PLANS.

FILE NAME : c:\pwworksp\pwworksp\sharer\jms\d9128316\0579663-shft-removal.dgn	USER NAME : sharer.jm	DESIGNED : JMS	REVISED : -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	REMOVAL SCHEDULES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE : 4R:8000' / 1" = 100'	CHECKED : -	DATE : 051011	REVISED : -		SCALE: NONE	SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.	12X,3RS-3 & 2RS-4	CHAMPAIGN	551	36
PLOT DATE : 10/18/2013	DATE : 051011	REVISED : -	REVISED : -						FAU 7152 & FAS 1512	CONTRACT NO. 70663		
ILLINOIS FED. AID PROJECT												