

BUT SHALL BE INCLUDED WITH THE PAY ITEM FOR STONE RIPRAP, CLASS A1.

THE EXCAVATION AND REMOVAL OF UNSUITABLE MATERIAL WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED WITH THE PAY ITEM FOR STONE RIPRAP, CALSS A1.

POROUS GRANULAR EMBANKMENT SHALL EXTEND 2 FT. BEYOND THE AGGREGATE SHOULDER

WORK SHOWN IN THE DETAIL SHALL BE PERFORMED IN ACCORDANCEWITH APPLICABLE PORTIONS OF SECTION 207 AND SECTION 540 OF THE STANDARD SPECIFICATIONS.

<i>Item</i>	Unit	Total
Porous Granular Embankment	Cu.Yd.	52.1
Stone Riprap, Class Al	Sq.Yd.	102.3

DRAWING NOT TO SCALE.

FILE NAME >	USEA NAME ≈ coarlockjd	DESIGNED - JMS	REVISED -		DETAIL OF POROUS GRANULAR EMBANKMENT				F.A.U.	SECTION	COUNTY	TOTAL SHEET
-ai\pw,work\pwidat\caarlackJd\d0128316\05	78663-sht-structures,dgn	DRAWN - RLA	REVISED -	STATE OF ILLINOIS					****	(2X.3)RS-3 & 2RS-4	CHAMPAIGN	551 196
]	PLOT SCALE = 40.0000 17 to.	CHECKED .	REVISED -	DEPARTMENT OF TRANSPORTATION					• F.A.U	. 7152 & F.A.S. 1512	CONTRACT	T NO. 70663
	PEOF DATE > 18/18/28/3 DATE - 0802!! REVISED -	REVISED -		SCALE: NONE	SHEET NO. 5 OF 6 SHEETS	STA.	TO STA.		ILLINOIS FED. AT			