

Benchmark: 675.112, Chiseled square on East end of south headwall of exist. A.R. box culvert, Sta. 289+49.7, 14.6' LT

Existing Structure: None.


**INDEX OF SHEETS**

1. Plan & Profile Sheet
2. General Plan and Elevation
- 3-4. Precast Concrete Box Culvert Apron End Section Details
5. Porous Granular Embankment Details


**GENERAL NOTES**

The design fill height for this box is < 2 feet. The precast box culvert sections shall conform to the requirements of AASHTO C 1577.  
 Drain holes shall be provided on exterior culvert walls for each precast box segment with a clear rise greater than 3 ft. The drain hole shall be located within 1/3 of the clear rise of the box culvert, shall not intercept the haunch, and shall conform to the requirements of Article 503.11 of the Standard Specification.  
 The 6 in. thick layer of porous granular material required for the precast concrete box culvert per Art. 540.06 of the Standard Specifications shall also apply to the end sections. Cost of the porous granular material will not be paid for separately but shall be included in the unit price of the work for which it is required.  
 Nonwoven geotextile fabric shall conform to the requirements of Art. 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard.

All exposed edges shall be chamfered 3/4" per article 503.06 of the Standard Specifications.




**ELEVATION**




**DRAIN DETAIL**

(All costs associated with furnishing and constructing the above drain details will not be measured for payment but shall be included in the contract unit price for the end section.)



**PLAN**



**PROFILE GRADE**

**DESIGN SPECIFICATIONS**

2012 AASHTO LRFD Bridge Design Specifications  
6th Edition

**LOADING HL-93**

**DESIGN STRESSES**


**PRECAST UNITS**

f'c = 5,000 psi  
fy = 65,000 psi (Welded Wire Fabric)

PROP. S.N. 010-8160  
STA. 286+30.00

STATION 286+30.00  
BUILT 2014 BY  
STATE OF ILLINOIS  
F.A.S. RT. 1512 US 150  
SEC. (2X,3)RS-3 & 2RS-4  
LOADING HL-93  
STR. NO. 010-8160

**NAME PLATE**  
See Std. 515001



**LOCATION SKETCH**

**GENERAL PLAN AND ELEVATION**  
**SINGLE 8' X 2' PRECAST BOX CULVERT**  
**F.A.S. ROUTE 1512 (US 150)**  
**SECTION (2X,3)RS-3 & 2RS-4**  
**CHAMPAIGN COUNTY**  
**STATION 286+30.00, S.N. 010-8160**  
**CULVERT NO. 8**

**TOTAL BILL OF MATERIAL**

ITEM	UNIT	TOTAL
Name Plates	Each	1.0
Box Culvert End Sections, Culvert No. 8	Each	2.0
Precast Concrete Box Culverts, 8' x 2'	Foot	39.0
Permanent Bench Marks	Each	1.0
Stone Riprap, Class A1	Sq. Yd.	96.1
Porous Granular Embankment	Cu. Yd.	20.6

**WATERWAY INFORMATION**

Drainage Area = 0.3 sq. mi. Low Grade Elev. 675.04 @ Sta. 283+50.00

Flood Yr.	Freq.	C.F.S.	Opening Sq. Ft.	Nat. H.W.E.	Head - Ft.	Headwater El.
			Exist. Prop.	Exist. Prop.	Exist. Prop.	Over
0						
10	46	4	14			673.3
Design	50	75	4	16		674.0
Base	100	88	4	16		674.2
Overtopping						
Max. Calc.	500	120	4	16		Over

**DESIGN SCOUR ELEVATION TABLE**

Design Scour Elevation (ft.)	Upstream	Downstream
	668.55	668.40