

DOUGLAS COUNTY STRUCTURE SCHEDULE OF QUANTITIES TRAFFIC CONTROL & PROTECTION

| COUNTY STRUCTURES TRAFFIC CONTROL & PROTECTION SCHEDULE | | | | | | | | | | | | | | | | | | | |
|---|-----------------|--------------------|---|-------------|-----------|----------|-------------------|------------------------------|--------|----------------------------|--------|----------|------------------------|--|--|--------------|---|-------|-------|
| | | | RAILROAD COORDINATION, N. A. ; MAINTENANCE ACTIVITY | | | | | TRAFFIC CONTROL & PROTECTION | | | | | PROSECUTION & PROGRESS | | | | | | |
| SN | ROUTE CARRIED | FEATURE CROSSED | OWNER | DOT/AAR NO. | MILE POST | FLAGGERS | INSURANCE (RRPLI) | 701400 | 701406 | 701411 (DRIVING LANE ONLY) | 701201 | 70200000 | LOC. | SUMMARY | CHANGEABLE MESSAGE SIGN (Calendar Days) | WORKING DAYS | PROSECUTION | RURAL | URBAN |
| 021-0001 | I-57 (NB) | CNRL RR/ BIKE PATH | | | | | | 2 | 2 | 1 | | | D25 | 4 - 701400 SET-UPS (2 DL; 2 PL) 4 - 701406 SET-UPS (2 DL; 2 PL) 2 - WD'S (1 DL; 1 PL) 2 STRUCTURES | | 2 | 1 DAY DRIVING LANES NB & SB; 1 DAY PASSING LANES NB & SB | X | |
| 021-0002 | I-57 (SB) | CNRL RR/ BIKE PATH | | | | | | 2 | 2 | | | | | | | | | X | |
| 021-0003 | I-57 (NB) | DRAINAGE DITCH | | | | | | INCL. | INCL. | | | | | | | | | X | |
| 021-0004 | I-57 (SB) | DRAINAGE DITCH | | | | | | INCL. | INCL. | | | | | | | | | X | |
| 021-0005 | I-57 (SB) | DRAINAGE DITCH | | | | | | 2 | 2 | | | | D27 | 4 - 701400 SET-UPS (2 DL; 2 PL) 4 - 701406 SET-UPS (2 DL; 2 PL) 4 - WD'S (2 DL; 2 PL) 6 STRUCTURES | 2 - CMS (1 NB; 1 SB); 7 CALENDAR DAYS PRIOR; 10 WORKING DAYS; 17 DAYS EACH DIRECTION; TOTAL 34 CALENDAR DAYS; 14 DOUGLAS COUNTY STRUCTURES ON FAI 57 | 4 | 2 DAY DRIVING LANES NB & SB; 2 DAY PASSING LANES NB & SB | X | |
| 021-0006 | I-57 (NB) | DRAINAGE DITCH | | | | | | 2 | 2 | | | | | | | | | X | |
| 021-0007 | I-57 (NB) | SCATTERING FORK | | | | | | INCL. | INCL. | | | | | | | | | X | |
| 021-0008 | I-57 (SB) | SCATTERING FORK | | | | | | INCL. | INCL. | | | | | | | | | X | |
| 021-0009 | I-57 (NB) | FAP 323(US 36) | | | | | | INCL. | INCL. | 1 | | | D26 | SEE SN 0212008 | | INCL. | SEE 0212008 | X | |
| 021-0010 | I-57 (SB) | FAP 323(US 36) | | | | | | INCL. | INCL. | 1 | | | | | | | | X | |
| 021-0011 | US 45(FAS 1671) | HAYES BRANCH | | | | | | | | | 2 | | D23 | 2 - 701201 (1 NB; 1 SB) 1 - WD'S (1 NB; 1 SB) 1 STRUCTURE | | 1 | 1/2 DAY NB; 1/2 DAY SB | X | |
| 021-0012 | US 45(FAS 1671) | SCATTERING FORK | | | | | | | | | | INCL. | D24 | SEE SN 0210060 | | INCL. | SEE SN 0210060 | X | |
| 021-0017 | FAP 323(US 36) | DRY FORK | | | | | | | | | 2 | | D2 | 2 - 701201 (1 EB; 1 WB) 1 - WD 1 STRUCTURE | | 0.5 | 1/4 DAY EB; 1/4 DAY WB | X | |
| 021-0018 | FAP 323(US 36) | KASKASKIA RIVER | | | | | | | | | 2 | | D1 | 2 - 701201 (1 EB; 1 WB) 1 - WD 1 STRUCTURE | | 0.5 | 1/4 DAY EB; 1/4 DAY WB | X | |
| 021-0020 | FAP 323(US 36) | HAYES BRANCH DITCH | | | | | | | | | 2 | | D8 | 6-701201 (3 EB; 3 WB) 2 - WD'S 3 STRUCTURES INCL. SN 0210057 & 0212026 | | 2 | 1 DAY EB; 1 DAY WB | X | |
| 021-0026 | FAP 749(IL 133) | DRAINAGE DITCH | | | | | | | | | 2 | | D19 | 2-701201 (1 EB; 1 WB) 1 - WD 2 STRUCTURES INCL. 0210055 | | 1 | 1/2 DAY EB; 1/2 DAY WB | X | |
| 021-0029 | IL 130(FAP 808) | EMBARRAS RIVER | | | | | | | | | 2 | | D9 | 2-701201 (1 NB; 1 SB) 1 - WD 1 STRUCTURE | | 1 | 1/2 DAY NB; 1/2 DAY SB | X | |
| 021-0030 | IL 130(FAP 820) | EMBARRAS RIVER | | | | | | | | | 2 | | D17 | 4-701201 (2 NB; 2 SB) 1 - WD 2 STRUCTURES | | 1 | 1/2 DAY NB; 1/2 DAY SB | X | |
| 021-0031 | IL 130(FAP 820) | SCATTERING FORK | | | | | | | | | 2 | | | | | | | X | |
| 021-0034 | FAS 522(CH 6) | I-57 | | | | | | | | | 2 | | D4 | 2-701201 (1 EB; 1 WB) 1 - WD 1 STRUCTURE | | 0.5 | 1/4 DAY EB; 1/4 DAY WB | X | |
| 021-0037 | TR 119 | I-57 | | | | | | | | | | 1 | D13 | 1-70200000 1/2 - WD 1 STRUCTURE | | 0.5 | 1/2 DAY CLOSURE | X | |
| 021-0041 | TR 157 D | I-57 | | | | | | | | | | 1 | D15 | 1-70200000 1/2 - WD 1 STRUCTURE | | 0.5 | 1/2 DAY CLOSURE | X | |
| 021-0043 | TR 25 | I-57 | | | | | | | | | | 1 | D5 | 1-70200000 1/2 - WD 1 STRUCTURE | | 0.5 | 1/2 DAY CLOSURE | X | |
| 021-0044 | TR 49 | I-57 | | | | | | | | | | 1 | D6 | 1-70200000 1/2 - WD 1 STRUCTURE | | 0.5 | 1/2 DAY CLOSURE | X | |
| 021-0045 | TR 83 | I-57 | | | | | | | | | | 1 | D11 | 1-70200000 1/2 - WD 1 STRUCTURE | | 0.5 | 1/2 DAY CLOSURE | X | |
| 021-0046 | TR 108 | I-57 | | | | | | | | | | 1 | D12 | 1-70200000 1/2 - WD 1 STRUCTURE | | 0.5 | 1/2 DAY CLOSURE | X | |
| 021-0049 | IL 130(FAP 820) | DEER CREEK | | | | | | | | | 2 | | D18 | 2-701201 (1 NB; 1 SB) 1 - WD 1 STRUCTURE | | 1 | 1/2 DAY NB; 1/2 DAY SB | X | |
| 021-0050 | US 36(FAP 323) | DRAINAGE DITCH | | | | | | | | | 2 | | D10 | 4-701201 (2 EB; 2 WB) 1 - WD 2 STRUCTURES INCLUDING SN 0212018 | | 1 | 1/2 DAY EB; 1/2 DAY WB | X | |
| 021-0051 | US 36(FAP 323) | LAKE FORK RIVER | | | | | | | | | 2 | | D3 | 2-701201 (1 EB; 1 WB) 1/2 WD 1 STRUCTURE | | 0.5 | 1/4 DAY EB; 1/4 DAY WB | X | |
| 021-0052 | FAP 323(US 36) | BRUSHY FORK RIVER | | | | | | | | | 2 | | D21 | 4-701201 (2 EB; 2 WB) 1 - WD 2 STRUCTURES INCLUDING SN 0212022 | | 1 | 1/2 DAY EB; 1/2 DAY WB | X | |

•FY2014 BRIDGE DECK SEALING
•DOUGLAS, EDGAR, & PIATT COUNTIES

| | | | | | | | | | | | |
|---|-----------------------|-----------------|-----------|---|---|--------------------|-------------------------|--------|--------------|---------------------------|--|
| FILE NAME = | USER NAME = ppersonbr | DESIGNED - TJB | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | DOUGLAS COUNTY STRUCTURE SCHEDULE OF QUANTITIES TRAFFIC CONTROL & PROTECTION | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| et:\pw\work\p\dot\personbr\d0312248\050918-sht-schedule.dgn | | DRAWN - DFJ | REVISED - | | | VAR | * | ** | 21 | 15 | |
| PLOT SCALE = 40.0000' / in. | | CHECKED - | REVISED - | | | CONTRACT NO. 70918 | | | | | |
| PLOT DATE = 11/21/2013 | | DATE - 08/15/12 | REVISED - | | | SCALE: NONE | SHEET NO. 1 OF 2 SHEETS | STA. | TO STA. | ILLINOIS FED. AID PROJECT | |