

PIATT COUNTY STRUCTURE SCHEDULE OF QUANTITIES ACTUAL MEASUREMENTS

PIATT COUNTY STRUCTURE SCHEDULE OF QUANTITIES ACTUAL MEASUREMENTS																								
			SIMS INFORMATION		DECK			APPROACH SLABS					PARAPETS (HUB, FACE & TOP)			TYPE B CURB (FACE & TOP)			GRAND TOTAL (SQ FT)	LOC.	RURAL	URBAN		
													HEIGHT	LENGTH		TOTAL AREA (SQ FT)	HEIGHT	LENGTH					TOTAL AREA (SQ FT)	
SN	ROUTE CARRIED	FEATURE CROSSED	LENGTH (FT)	0-0 WIDTH (FT)	LENGTH (E-E)	WIDTH (F-F)	TOTAL AREA (SQ FT)	TOTAL LENGTH (FT)	LENGTH INSIDE PARAPET (FT)	WIDTH INSIDE PARAPET (FT)	LENGTH BEYOND PARAPET (FT)	WIDTH BEYOND PARAPET (0-0)	TOTAL AREA (SQ FT)	4.15 FT TYPICAL	ALONG DECK (FT)	ALONG APPR. (FT)	TOTAL AREA (SQ FT)	9 INCH TYPICAL	ALONG APPR. PVT.	TOTAL AREA (SQ FT)				
074-0001	I-72 (EB)	IC RR	151.7	41.6	149.4	38.4	5735.8	29.5	14.76	38.4	14.8	41.6	2362.4	4.15	149.4	14.8	1484.8	0.75	14.8	44.3	9628	P17	X	
074-0002	I-72 (WB)	IC RR	151.7	41.6	149.4	38.4	5735.8	29.5	14.76	38.4	14.8	41.6	2362.4	4.15	149.4	14.8	1484.8	0.75	14.8	44.3	9628		X	
074-0005	IL 10 (FAP 721)	MADDEN CREEK	151.4	32.0	149.1	32.0	4770.2	0.0	0	32.0	0.0	32.0	0.0	0.00	149.1	0.0	0.0	0.75	0.0	0.0	4771	P6	X	
074-0007	IL 10 (FAP 721)	I-72	269.2	36.2	266.9	33.0	8806.7	30.0	0	33.0	30.0	36.2	2172.0	4.15	266.9	0.0	2215.0	0.75	30.0	90.0	13284	P8	X	
074-0013	IL 48(FAP 760)	CREEK	32.0	42.2	29.7	38.5	1142.3	20.0	0	38.5	20.0	42.2	1688.0	0.00	29.7	0.0	145.7	0.75	5.0	15.0	2992	P12	X	
074-0015	IL 48(FAP 760)	CREEK	47.6	35.2	45.3	32.0	1448.6	20.0	0	32.0	20.0	35.2	1330.0	4.15	45.3	0.0	375.7	0.75	5.0	15.0	3170	P13	X	
074-0016	IL 48(FAP 760)	CREEK	25.4	42.2	23.1	38.5	888.2	20.0	0	38.5	20.0	42.2	1688.0	0.00	23.1	0.0	117.6	0.75	5.0	15.0	2709		X	
074-0021	FAS 538(BRIDGE ST)	SANGAMON RIVER	530.7	39.2	528.4	36.0	19021.3	30.0	13.5	36.0	16.5	39.2	2265.6	4.15	528.4	13.5	4609.6	0.75	16.5	49.5	25946	P19		X
074-0030	IL 105(FAP 741)	CREEK	29.0	45.3	26.7	42.3	1128.9	20.0	0	42.3	20.0	45.3	1812.0	2.25	26.7	0.0	120.0	0.75	5.0	15.0	3076	P23	X	
074-0035	TR 87	I-72	223.2	27.7	220.9	22.0	4859.1	0.0	0	22.0	0.0	27.7	0.0	3.32	220.9	0.0	1466.6	0.75	0.0	0.0	6715	P18	X	
074-0036	FAS 1532 (TR 154)	I-72	233.4	29.8	231.1	24.0	5545.7	0.0	0	24.0	0.0	29.8	0.0	3.32	231.1	0.0	1534.3	0.75	0.0	0.0	7469	P9	X	
074-0040	TR 80	I-74	254.9	30.0	252.6	28.0	7072.0	0.0	0	28.0	0.0	30.0	0.0	3.32	252.6	0.0	1677.1	0.75	0.0	0.0	8750	P1	X	
074-0041	TR 96	I-74	260.6	30.0	258.3	28.0	7231.6	0.0	0	28.0	0.0	30.0	0.0	3.32	258.3	0.0	1714.9	0.75	0.0	0.0	8947	P2	X	
074-0044	FAS 495	I-74	251.7	68.0	249.4	64.8	16159.2	0.0	0	64.8	0.0	68.0	0.0	4.32	249.4	0.0	2154.6	0.75	0.0	0.0	18314	P3	X	
074-0055	IL 48 (FAP 760)	I-72	250.8	68.0	248.5	64.8	16338.9	0.0	0	64.8	0.0	68.0	155.0	3.46	248.5	5.0	1788.6	0.75	5.0	15.0	18298	P14	X	
074-0063	I-72 (EB)	WILDCAT CREEK	107.2	42.0	104.9	38.8	4069.0	0.0	0	38.8	0.0	42.0	0.0	3.43	104.9	0.0	719.4	0.75	0.0	0.0	4789	P22	X	
074-0064	I-72 (WB)	WILDCAT CREEK	107.2	42.0	104.9	38.8	4069.0	0.0	0	38.8	0.0	42.0	0.0	3.43	104.9	0.0	719.4	0.75	0.0	0.0	4789		X	
074-0067	I-72 (EB)	SANGAMON RIVER	677.9	42.0	675.6	38.5	26009.4	0.0	0	38.5	0.0	42.0	2928.7	3.32	675.6	0.0	4485.8	0.75	0.0	0.0	33424	P10		X
074-0068	I-72 (WB)	SANGAMON RIVER	677.9	42.0	675.6	38.5	26009.4	0.0	0	38.5	0.0	42.0	2928.7	3.32	675.6	0.0	4485.8	0.75	0.0	0.0	33424			X
074-0076	IL 10(FAP 721)	SANGAMON RIVER	590.0	34.0	587.7	32.0	18805.4	0.0	0	32.0	0.0	34.0	0.0	4.15	587.7	13.5	5101.8	0.75	0.0	0.0	23908	P7	X	
074-0079	IL 105(FAP 741)	CREEK	52.5	43.2	50.2	40.0	2006.8	20.0	0	40.0	20.0	43.2	1470.6	4.15	50.2	0.0	416.4	0.75	5.0	15.0	3909	P21	X	
074-0080	IL 105(FAP 741)	STREAM	42.0	43.2	39.7	40.0	1586.8	20.0	0	40.0	20.0	43.2	1470.6	4.15	39.7	0.0	329.3	0.75	5.0	15.0	3402	P20	X	
074-0081	IL 48(FAP 760)	STREAM	82.0	35.2	79.7	32.0	2549.4	20.0	0	32.0	20.0	35.2	1470.6	4.15	79.7	0.0	661.3	0.75	5.0	15.0	4697	P12	X	
074-0082	IL 48(FAP 760)	FRIENDS CREEK DITCH	147.5	35.2	145.2	32.0	4645.4	20.0	0	32.0	20.0	35.2	1287.0	4.15	145.2	0.0	1204.9	0.75	5.0	15.0	7153	P13	X	
074-0084	FAS 1517(US 150)	MADDEN CREEK	66.5	35.2	64.2	32.0	2053.4	30.0	0	32.0	30.0	35.2	2112.0	4.15	64.2	0.0	532.6	0.75	30.0	90.0	4789	P5	X	
074-0086	US 150 (FAS 1517)	N & W RR	164.0	35.2	161.7	32.0	5173.4	30.0	15	32.0	15.0	35.2	2016.0	4.15	161.7	15.0	1590.9	0.75	15.0	45.0	8826	P4	X	
074-0087	FAS 1517 (US 150)	S BRANCH SALT CREEK	113.0	35.2	110.7	32.0	3541.4	30.0	15	32.0	15.0	35.2	2016.0	4.15	110.7	15.0	1167.6	0.75	15.0	45.0	6771	P11	X	
074-2003	FAP 758(IL 32)	STREAM	45.3	63.8	43.0	32.0	1375.0	30.0	0	32.0	30.0	35.0	2100.0	2.25	43.0	0.0	193.4	0.75	30.0	90.0	3759	P16	X	
074-3171	FAP 760 (CH 17)	SANGAMON RIVER	372.0	36.2	369.7	34.0	12568.8	30.0	15	34.0	15.0	36.2	2820.0	4.15	369.7	15.0	3317.3	0.75	0.0	0.0	18707	P15	X	

GRAND TOTAL (SQ FT): 306044 213250 92794

•FY2014 BRIDGE DECK SEALING
•DOUGLAS, EDGAR, & PIATT COUNTIES