

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY BRRP	BOX CULVERT BRRP	OVERFLOW BRIDGE BRRP	BRIDGE REPAIR BRRP
				80 FED / 20 ST RURAL 0004	80 FED / 20 ST S. N. 054-7069 0040	80 FED / 20 ST S. N. 054-0515 0011	80 FED / 20 ST S. N. 054-0009 0014
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1	
50102400	CONCRETE REMOVAL	CU YD	20.2				20.2
50105220	PIPE CULVERT REMOVAL	FOOT	62	27		35	
50200100	STRUCTURE EXCAVATION	CU YD	848		643	205	
50300100	FLOOR DRAINS	EACH	12			12	
50300225	CONCRETE STRUCTURES	CU YD	103.4			103.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	300.8			278.1	22.7
50300260	BRIDGE DECK GROOVING	SO YD	1,522			639	883
50300280	CONCRETE ENCASEMENT	CU YD	2.1			2.1	
50300300	PROTECTIVE COAT	SO YD	900			825	75
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2,016				2,016
50500505	STUD SHEAR CONNECTORS	EACH	2,430			2,430	

14

FILE NAME : c:\p\work\p\dat\sparkag\10219096\067	USER NAME : sparkag 1002-101-500.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE : 100.000' / in.	CHECKED -	REVISED -	717					1102B-1,102CR,102BR-2IRS-5	LOGAN	218	7	
PLOT DATE : Dec-04-2013 09:51:01AM	DATE -	REVISED -			SCALE:	SHEET NO. 4 OF 10 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 72882	