	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: ROADWAY BRRP 80 FED / 20 ST RURAL 0004	BOX CULVERT BRRP 80 FED / 20 ST S. N. 054-7069 0040	OVERFLOW BRIDGE BRRP 80 FED / 20 ST S. N. 054-0515 0011	BRIDGE REPAIR BRRP 80 FED / 20 ST S. N. 054-0009 0014
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9,034		2,944	4,534	1,556
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	875		350		525
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	825		325		500
	70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	8		2	4	2
	70600332	IMPACT ATTENUATORS, RELOCATE (FULLYREDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4		2		2
*	72000100	SIGN PANEL - TYPE 1	SQ FT	29	29			
*	73000100	WOOD SIGN SUPPORT	FOOT	60	60			
*	78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	15,339	15,339			
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	47	47			
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	59	30	10	19	
*	78200420	GUARDRAIL MARKERS, TYPE B	EACH	5			5	
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12		4	4	4
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	6,415		1,589	3,438	1,388
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	44		17	26	1

14

* SPECIALTY ITEM

BLANK, WESSELINK, COOK & ASSOCIATES ENGINEERS - CONSULTANTS DECATUR, ILLINOIS

FILE NAME = c:\pw_work\pwidot\sparkagw\d0219896\D672882-sht-S00.dgn	USER NAME = sparkagw	DESIGNED -	REVISED -
	PLOT SCALE = 100.000 ' / in.	DRAWN -	REVISED -
	PLOT DATE = Dec-04-2013 08:51:04AM	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 8 OF 10 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	(102B-1,102CR,102BR-2)RS-5	LOGAN	218	11

CONTRACT NO. 72882

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT