

WIDENING SCHEDULE

STATION TO STATION	LOCATION	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 10'	PAVEMENT FABRIC
	CORNER	SO YD	SO YD
S. N. 096-0010			
	NE	46.7	46.7
	NW	46.7	46.7
	SE	46.7	46.7
	SW	46.7	46.7
S. N. 096-0061			
	NE	48.6	48.6
	NW	50.9	50.9
	SE	45.5	45.5
	SW	45.9	45.9
TOTAL:		378	378

PAVING SCHEDULE

STATION TO STATION	HOT MIX ASPHALT SURFACE COURSE, MIX C, N70	HOT MIX ASPHALT SURFACE REMOVAL 1 1/2"	TEMPORARY RAMP
	TON	SO YD	SO YD
S. N. 096-0010			
	EAST	2.3	27.8
	WEST	2.3	27.8
S. N. 096-0061			
	EAST	0.0	0.0
	WEST	2.3	27.8
TOTAL:		7	84

TRAFFIC CONTROL DEVICES SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	FOOT	FOOT	EACH	EACH
S. N. 096-0010				
483+16 TO 498+48	1537.5	1537.5	2.0	2.0
S. N. 096-0061				
345+75 TO 352+66	700.0	700.0	2.0	2.0
TOTALS		2237.5	2237.5	4.0

PAVEMENT MARKING SCHEDULE

STATION TO STATION	PAINT PAVEMENT MARKING - LINE 4"	PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING 4"	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	FOOT	SO FT	FOOT	FOOT	SO FT
S. N. 096-0010					
481+65 TO 500+00	4129	1376	4129	184	61
S. N. 096-0061					
346+00 TO 354+00	1800	600	1800	80	27
TOTALS		5929	1976	5929	264