

TEMPORARY RAMP SCHEDULE

LOCATION	COMMENTS	ENTRANCE MATERIAL	SIDE	LENGTH	WIDTH	TEMPORARY RAMP
STATION			LT/RT	FOOT	FOOT	SQ YD
555+55.00	BEGIN PROJECT			24	3	8
558+47.07	WOODY ROAD (1000N)	O&C	RT	3	80	26.7
558+52.41	WOODY ROAD (1000N)	O&C	LT	3	80	26.7
596+00.48	ALTERNATIVE 267	O&C	RT	3	40	13.3
609+56.76	ALTERNATIVE 267	O&C	RT	3	65	21.7
610+81.18	DOGWOOD DRIVE	CONC	RT	3	60	20
614+42.26	JACK PINE DRIVE	O&C	RT	3	60	20
615+59.06	GOLDEN EAGLE	CONC	LT	3	60	20
618+68.11	KC DRIVE	CONC	LT	3	55	18.3
633+51.89	PRIVATE ENTRANCE	O&C	LT	3	35	11.7
639+02.81	PONDEROSA LANE	O&C	LT	3	45	15
641+58.42	STORAGE UNITS	O&C	LT	3	60	20
642+01.92	PRIVATE ENTRANCE	O&C	LT	3	20	6.7
644+73.21	PRIVATE ENTRANCE	CONC	LT	3	35	11.7
648+73.99	EVANS FORD-MERCURY INC	BIT	RT	3	55	18.3
648+93.42	PRIVATE ENTRANCE	BIT	LT	3	25	8.3
650+02.52	EVANS FORD-MERCURY INC	BIT	RT	3	50	16.7
652+39.22	COMMERCIAL ENTRANCE	BIT	LT	3	30	10
653+09.21	COMMERCIAL ENTRANCE	BIT	LT	3	40	13.3
654+99.17	PRIVATE ENTRANCE	BIT	RT	3	20	6.7
656+58.30	TERESA STREET	O&C	RT	3	40	13.3
657+62.03	COMMERCIAL ENTRANCE	CONC	RT	3	50	16.7
658+40.23	PRIVATE ENTRANCE	O&C	LT	3	35	11.7
658+87.64	PRIVATE ENTRANCE	BIT	RT	3	30	10
660+05.10	PRIVATE ENTRANCE	BIT	RT	3	30	10
660+29.14	PRIVATE ENTRANCE	BIT	LT	3	20	6.7
660+62.01	PRIVATE ENTRANCE	BIT	RT	3	25	8.3
662+33.08	PRIVATE ENTRANCE	BIT/AGG	RT	3	35	11.7
663+25.31	PRIVATE ENTRANCE	BIT/AGG	RT	3	25	8.3
664+38.01	PRIVATE ENTRANCE	O&C	RT	3	20	6.7
665+31.05	EAST CEMETERY ROAD	BIT	RT	3	40	13.3
665+56.72	WEST CEMETERY ROAD	BIT	LT	3	40	13.3
666+61.58	PRIVATE ENTRANCE	BIT	RT	3	35	11.7
666+68.78	PRIVATE ENTRANCE	CONC	LT	3	15	5
668+51.04	PRIVATE ENTRANCE	BIT/AGG	RT	3	25	8.3
669+59.74	PRIVATE ENTRANCE	BIT	RT	3	25	8.3
670+61.61	PRIVATE ENTRANCE	CONC	RT	3	35	11.7
670+62.35	PRIVATE ENTRANCE	BIT/AGG	LT	3	20	6.7
672+78.89	VIRGINIA AVENUE	BIT	RT	3	50	16.7
673+87.69	PRIVATE ENTRANCE	BIT	LT	3	25	8.3
676+17.65	ALLEY	O&C	LT	3	20	6.7
676+84.82	PRIVATE ENTRANCE	BIT	RT	3	25	8.3
678+89.81	PRIVATE ENTRANCE	BIT	RT	3	25	8.3
678+96.01	COMMERCIAL ENTRANCE	BIT	LT	3	25	8.3
679+70.86	COMMERCIAL ENTRANCE	BIT	LT	3	55	18.3
680+30.10	COMMERCIAL ENTRANCE	BIT	LT	3	35	11.7
680+72.67	PINE STREET	BIT	RT	3	45	15
681+13.68	COMMERCIAL ENTRANCE	BIT	LT	3	35	11.7
SUBTOTAL A						608.1

TEMPORARY RAMP SCHEDULE

LOCATION	COMMENTS	ENTRANCE MATERIAL	SIDE	LENGTH	WIDTH	TEMPORARY RAMP
STATION			LT/RT	FOOT	FOOT	SQ YD
681+53.32	COMMERCIAL ENTRANCE	BIT	LT	3	40	13.3
682+53.44	ALLEY	BIT	RT	3	45	15
683+10.47	COMMERCIAL ENTRANCE	BIT	LT	3	60	20
684+28.48	SCHOOL STREET	BIT	LT	3	50	16.7
684+58	SIDEWALK		LT	3	4	1.3
684+58	SIDEWALK		RT	3	4	1.3
684+97	SIDEWALK		LT	3	4	1.3
686+49.38	ALLEY	BIT	LT	3	20	6.7
686+86.77	COMMERCIAL ENTRANCE	CONC	RT	3	30	10
687+41.46	COMMERCIAL ENTRANCE	CONC	RT	3	40	13.3
688+42	SIDEWALK		LT	3	4	1.3
688+42	SIDEWALK		RT	3	4	1.3
688+71.07	EAST SYCAMORE STREET	BIT	RT	3	40	13.3
688+71.07	WEST SYCAMORE STREET	BIT	LT	3	40	13.3
689+66.52	PRIVATE ENTRANCE	CONC/AGG	RT	3	20	6.7
689+73.54	PRIVATE ENTRANCE	BIT/AGG	LT	3	20	6.7
690+89.51	ALLEY	CONC/O&C	LT	3	20	6.7
690+90.02	ALLEY	CONC/O&C	RT	3	20	6.7
691+92.59	COMMERCIAL ENTRANCE	CONC	LT	3	35	11.7
693+09.01	MAPLE STREET	BIT	RT	3	45	15
693+09.01	MAPLE STREET	BIT	LT	3	45	15
693+39	SIDEWALK		LT	3	4	1.3
693+39	SIDEWALK		RT	3	4	1.3
693+73.54	COMMERCIAL ENTRANCE	CONC/BIT	LT	3	35	11.7
693+76.10	COMMERCIAL ENTRANCE	CONC	RT	3	30	10
694+90.46	COMMERCIAL ENTRANCE	CONC	LT	3	40	13.3
695+28.59	ALLEY	CONC/O&C	LT	3	30	10
695+28.82	ALLEY	CONC/O&C	RT	3	30	10
696+42.28	COMMERCIAL ENTRANCE	CONC	RT	3	35	11.7
696+71.17	COMMERCIAL ENTRANCE	CONC	LT	3	40	13.3
696+86.48	COMMERCIAL ENTRANCE	CONC	RT	3	45	15
697+21	SIDEWALK		LT	3	4	1.3
697+21	SIDEWALK		RT	3	4	1.3
697+46.87	LOCUST STREET	BIT	LT	3	45	15
697+49.93	LOCUST STREET	BIT	RT	3	45	15
697+80	SIDEWALK		LT	3	4	1.3
697+80	SIDEWALK		RT	3	4	1.3
698+21.59	COMMERCIAL ENTRANCE	BIT/CONC	RT	3	50	16.7
698+50.86	COMMERCIAL ENTRANCE	CONC/AGG	LT	3	25	8.3
699+30.51	COMMERCIAL ENTRANCE	CONC/AGG	LT	3	20	6.7
699+34.27	COMMERCIAL ENTRANCE	BIT/CONC	RT	3	55	18.3
699+71.12	ALLEY	BIT	LT	3	25	8.3
699+71.12	ALLEY	BIT	RT	3	25	8.3
700+19.09	COMMERCIAL ENTRANCE	CONC	RT	3	40	13.3
700+70.00	COMMERCIAL ENTRANCE	CONC	RT	3	40	13.3
701+61	SIDEWALK		LT	3	6	2
701+61	SIDEWALK		RT	3	4	1.3
701+86.93	SOUTH MAIN STREET	BIT	LT	3	45	15
SUBTOTAL B						440.9

TEMPORARY RAMP SCHEDULE

LOCATION	COMMENTS	ENTRANCE MATERIAL	SIDE	LENGTH	WIDTH	TEMPORARY RAMP
STATION			LT/RT	FOOT	FOOT	SQ YD
701+86.93	SOUTH MAIN STREET	BIT	RT	3	50	16.7
702+35.00	COMMERCIAL ENTRANCE	BIT	LT	3	45	15
704+05.00	ALLEY	BIT	RT	3	15	5
705+65.00	COMMERCIAL ENTRANCE	BIT	LT	3	50	16.7
706+14.49	NORTH MAIN STREET	BIT	LT	3	50	16.7
706+28.38	NORTH MAIN STREET	BIT	RT	3	50	16.7
706+58	SIDEWALK		LT	3	6	2
706+58	SIDEWALK		RT	3	4	1.3
708+29.50	COMMERCIAL ENTRANCE	CONC	RT	3	15	5
708+47.00	ALLEY	CONC/O&C	RT	3	25	8.3
708+47.00	ALLEY	CONC/O&C	LT	3	25	8.3
708+79.50	COMMERCIAL ENTRANCE	CONC	LT	3	30	10
708+86.00	COMMERCIAL ENTRANCE	CONC	RT	3	60	20
709+81.00	COMMERCIAL ENTRANCE	CONC/BIT	RT	3	50	16.7
710+40.00	COMMERCIAL ENTRANCE	CONC/BIT	RT	3	15	5
710+66.62	CHURCH STREET	BIT	RT	3	40	13.3
710+68.31	CHURCH STREET	BIT	LT	3	40	13.3
710+97	SIDEWALK		LT	3	4	1.3
710+97	SIDEWALK		RT	3	4	1.3
711+26.60	COMMERCIAL ENTRANCE	CONC/BIT	LT	3	40	13.3
712+86.16	ALLEY	CONC	RT	3	20	6.7
712+86.16	ALLEY	CONC	LT	3	20	6.7
714+83.30	EAST WALNUT STREET	BIT	RT	3	50	16.7
717+76.15	COMMERCIAL ENTRANCE	CONC/BIT	LT	3	50	16.7
718+99.12	COMMERCIAL ENTRANCE	CONC	LT	3	35	11.7
719+64.16	PARKVIEW STREET	BIT	RT	3	55	18.3
720+10.44	PARKVIEW DRIVE	BIT	LT	3	50	16.7
723+69.13	PRIVATE ENTRANCE	BIT	RT	3	25	8.3
724+79.71	PRIVATE ENTRANCE	BIT	RT	3	25	8.3
729+21.75	6TH STREET	BIT	LT	3	110	36.7
729+97.42	COMMERCIAL ENTRANCE	BIT	RT	3	25	8.3
731+31.26	COMMERCIAL ENTRANCE	CONC	RT	3	35	11.7
731+78.65	COMMERCIAL ENTRANCE	CONC	RT	3	20	6.7
732+45.61	COMMERCIAL ENTRANCE	CONC	RT	3	20	6.7
746+88.96	PRIVATE ENTRANCE	BIT	RT	3	15	5
748+32.99	PRIVATE ENTRANCE	BIT	RT	3	30	10
755+76.33	MICHELLE LANE	BIT	RT	3	45	15
758+75.21	PRIVATE ENTRANCE	CONC/AGG	RT	3	40	13.3
773+21.64	TR 207 (1400N)	O&C	LT	3	45	15
813+11.41	TR 205 (1475N)	O&C	RT	3	65	21.7
826+28.25	CEMETARY ROAD (1500N)	O&C	LT	3	55	18.3
831+60.00	END PROJECT			24	3	8
SUBTOTAL C						492.4
SUBTOTAL A						608.1
SUBTOTAL B						440.9
SUBTOTAL C						492.4
TOTAL						1541.4