



CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				URBAN	100% STATE
				BRIDGE 0014	S. N. 082-0037
20300100	CHANNEL EXCAVATION	CU YD	185	185	
28100107	STONE RIPRAP, CLASS A4	SO YD	695	695	
28200200	FILTER FABRIC	SO YD	695	695	
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SO YD	145	145	
44004250	PAVED SHOULDER REMOVAL	SO YD	145	145	
50102400	CONCRETE REMOVAL	CU YD	4	4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.8	3.8	
50300260	BRIDGE DECK GROOVING	SO YD	431	431	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	290	290	
50800515	BAR SPLICERS	EACH	8	8	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	78	78	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				URBAN	100% STATE
				BRIDGE 0014	S. N. 082-0037
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	16	16	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	337	337	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	775	775	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	118	118	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	387.5	387.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	387.5	387.5	
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	337	337	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	
* 78200430	GUARDRAIL MARKERS, TYPE C	EACH	12	12	
78300100	PAVEMENT MARKING REMOVAL	SO FT	27	27	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6	

* SPECIALTY ITEM

FILE NAME =	USER NAME = tharpf	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
or\p\work\p\dot\tharpf\1\034004\1\08760	41-shaata.plandgn	DRAWN -	REVISED -					327	3BR-1-1-1	ST. CLAIR	20	3
PLOT SCALE = 100.0000 1/4"	CHECKED -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		
PLOT DATE = 12/22/2013	DATE -	REVISED -			CONTRACT NO. 76G41							

2/19/2014