F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
908	09-00481-00-WR	CHAMPAIGN	193	5
STA.		TO STA.		
FED. ROAD DIST. NO. 5	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 91506

SUMMARY OF QUANTITIES			CHAMPAIGN COUNTY ROADWAY CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	0003
40701911	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/2"	SQ YD	32,994
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	1,472
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	55
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	142
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	5,496
42400800	DETECTABLE WARNINGS	SQ FT	333
44000100	PAVEMENT REMOVAL	SQ YD	14,502
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	9,024
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,968
44000600	SIDEWALK REMOVAL	SQ FT	2,588
44003100	MEDIAN REMOVAL	SQ FT	4,772
44004250	PAVED SHOULDER REMOVAL	SQ YD	7,794
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	66
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	277

1 Rev. 2-12-14

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES
IL. RTE 130

SCALE:
DRAWN BY: MJO
DATE: 12/09/13
CHECKED BY: KLT

SUMMARY OF QUANTITIES: IL. RTE. 130

500.03
L:\Urbana\2009-08\Draw\CADD_Sheets\SummaryOfQuantities.dgn
12/6/2013