CODE NO.	ITEM	UNIT	100% STATE TOTAL QUANTITY	CONSTR. CODE BRIDGE 0014 S. N. 060-0237
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	192	192
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	426	426
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	77	77
44004250	PAVED SHOULDER REMOVAL	SQ YD	89	89
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	356	356
50102400	CONCRETE REMOVAL	CU YD	19.6	19.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	37	37
50300300	PROTECTIVE COAT	SQ YD	94	94
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3970	3970
50800515	BAR SPLICERS	EACH	48	48
50800530	MECHANICAL SPLICERS	EACH	152	152
52000110	PREFORMED JOINT STRIP SEAL	FOOT	74.5	74.5
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	420	420
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3

1

14

1 REV. 2-17-17

FILE NAME = pw:\\IL084EBIDINTEG.illinois.gov:PWIDOT\Documents\IDOT Offices\District 8\Projects\D876J78-sht-plan.dgn	USER NAME = simam	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P RTE. 785	SECTION 134B-R-2	COUNTY MADISON	TOTAL SHEETS 16	SHEET NO. 3
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -		SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.			CONTRACT NO. 76J78		
	PLOT DATE = 12/23/2016	DATE -	REVISED -				ILLINOIS FED. AID PROJECT			