CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE 80% FED 20% STATE BRIDGE 0014 031-0001
X0320622	FIELD MEASUREMENTS	L SUM	1	1
X0326563	SPAN BALANCE	L SUM	1	1
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X7016500	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	EACH	12	12
X7200200	WIDE LOAD SIGNING	L SUM	1	1
X7800200	PAINT PAVEMENT MARKING CURB	FOOT	40	40
Z0001905	STRUCTURAL STEEL REPAIR	POUND	19170	19170
* Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1
* Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1
Z0012193	BRIDGE DECK THIN POLYMER OVERLAY 3/8"	SQ YD	791	791
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	2	2
X1000001	THIN POLYMER OVERLAY REMOVAL	SQ YD	791	791
Z0015500	DEBRIS REMOVAL	L SUM	1	1
∅ Z0076600	TRAINEES	HOUR	1500	1500
Z0021908	SILICONE JOINT SEALER, 2"	FOOT	25	25
∅ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1500	1500
Z0021916	SILICONE JOINT SEALER, 3"	FOOT	25	25

12

* SPECIALTY ITEMS

∅ 0042

1 REVISED 2-19-16

FILE NAME = pw:\\IL084EBIDINTEG.illinois.gov:PWIDOT\Documents\IDOT Offices\District 8\Projects\DB75HD\DB76HD\Data\EADsheets\DB76HD6-sht-SOD.dgn	USER NAME = DuroseJ	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/16/2015	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 3 OF 3 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	266BR-1	GREENE	27	5

CONTRACT NO. 76H06

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT