

URBAN 801.FED./201.STATE

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 1000-2A	BRIDGE SN 022-0033 X271-2A	VILLAGE OF LISLE X271-2A 100% L.A.
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	432		432	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4		
40600300	AGGREGATE (PRIME COAT)	TON	19	19		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	524	524		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	62	62		
40603395	HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	443	443		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	74	74		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	4,520	4,520		
44000600	SIDEWALK REMOVAL	SQ FT	365	365		
44000700	APPROACH SLAB REMOVAL	SQ YD	440	440		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	146	146		
44003700	MEDIAN REMOVAL (SPECIAL)	SQ FT	2,874	2,874		
50102400	CONCRETE REMOVAL	CU YD	60.6		60.6	
50104650	SLOPE WALL REMOVAL	SQ YD	5.6		5.6	
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1	
50157300	PROTECTIVE SHIELD	SQ YD	871		871	
50200100	STRUCTURE EXCAVATION	CU YD	489.4		489.4	
50300100	FLOOR DRAINS	EACH	8		8	
50300225	CONCRETE STRUCTURES	CU YD	73.6		73.6	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	713.1		713.1	
50300260	BRIDGE DECK GROOVING	SQ YD	1,200		1,200	
50300285	FORM LINER TEXTURED SURFACE	SQ FT	1,284			1,284
50300300	PROTECTIVE COAT	SQ YD	2,169	344	1,825	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	330		330	
50500505	STUD SHEAR CONNECTORS	EACH	5,664		5,664	
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1		1	
50606600	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES	L SUM	1		1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	137,440		137,440	
50800515	BAR SPLICERS	EACH	797		797	
51100100	SLOPE WALL 4 INCH	SQ YD	5.6		5.6	
51500100	NAME PLATES	EACH	1		1	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24	
52100520	ANCHOR BOLTS, 1"	EACH	48		48	
59000200	EPOXY CRACK INJECTION	FOOT	12		12	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	177		177	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	177		177	
60619500	CONCRETE MEDIAN, TYPE SB-6.06 (SPECIAL)	SQ FT	2,874	2,874		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4	

\* SPECIALTY ITEM

801.FED./201.STATE

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 1000-2A	BRIDGE SN 022-0033 X271-2A	VILLAGE OF LISLE X271-2A 100% L.A.
63200310	GUARDRAIL REMOVAL	FOOT	179	179		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
67100100	MOBILIZATION	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,290	1,290		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,260	3,260		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	520	520		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	488	488		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,758	2,758		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	64	64		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	621	621		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	116	116		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	19	19		
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	42	42		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,003	1,003		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	116	116		
* 81100700	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., GALVINIZED STEEL	FOOT	30	30		
* 81300835	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18"X18"X10"	EACH	2	2		
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	73	73		
* 89502200	MODIFY EXISTING CONTROLLER	EACH	2	2		
* 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	2,950	2,950		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	214	214		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	164		164	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	20		20	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	8,490	8,490		
* X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1	1		
X0326096	ALUMINUM RAILING, SPECIAL	FOOT	300		300	
* XX003079	REMOVE JUNCTION BOX	EACH	2	2		
XX007023	STAINING CONCRETE STRUCTURES	SQ YD	186.2		186.2	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		
Z0030390	IMPACT ATTENUATORS, REPLACEMENT (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		
Z0031200	JACKING AND CRIBBING	EACH	24	24		
Δ Z0076600	TRAINEES	HOUR	500	500		

\* SPECIALTY ITEM

Δ Y080

PLOT DATE = 8/7/2009  
 PLOT SCALE = 1"=100'  
 USER NAME = jtracey  
 MODEL = Default



200 West Front Street  
Wh. .ion, IL 60187

DESIGNED -	REVISED -
DRAWN - MH	REVISED -
CHECKED - MK	REVISED -
DATE - 8/7/09	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**US RTE. 34 OVER IL RTE. 53  
STRUCTURE NO. 022-0033**

**SUMMARY OF  
QUANTITIES**

F.A.P. RTE. 311	SECTION 10HB-R	COUNTY	TOTAL SHEETS 53	SHEET NO. 3
CONTRACT NO. 60892			Rev. 2-11-10	

SCALE: SHEET NO. 3 OF 53 SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT