

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROADWAY

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+18.56	0.00	684.98	684.98
☉ Brg. W. Abut.	644+20.40	0.00	684.99	684.99
A	644+30.40	0.00	685.03	685.04
B	644+40.40	0.00	685.07	685.08
C	644+50.40	0.00	685.11	685.11
☉ Brg. ☉ Pier 1	644+61.90	0.00	685.14	685.14
D	644+71.90	0.00	685.16	685.18
E	644+81.90	0.00	685.17	685.20
F	644+91.90	0.00	685.18	685.22
G	645+01.90	0.00	685.17	685.22
H	645+11.90	0.00	685.17	685.20
I	645+21.90	0.00	685.15	685.16
☉ Brg. ☉ Pier 2	645+28.56	0.00	685.14	685.14
J	645+38.56	0.00	685.11	685.11
K	645+48.56	0.00	685.08	685.08
L	645+58.56	0.00	685.04	685.04
☉ Brg. E. Abut.	645+70.06	0.00	684.98	684.98
Back E. Abut.	645+71.90	0.00	684.97	684.97

STAGE CONSTRUCTION LINE

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+18.56	0.50	684.97	684.97
☉ Brg. W. Abut.	644+20.40	0.50	684.98	684.98
A	644+30.40	0.50	685.03	685.03
B	644+40.40	0.50	685.07	685.07
C	644+50.40	0.50	685.10	685.10
☉ Brg. ☉ Pier 1	644+61.90	0.50	685.13	685.13
D	644+71.90	0.50	685.15	685.17
E	644+81.90	0.50	685.16	685.20
F	644+91.90	0.50	685.17	685.21
G	645+01.90	0.50	685.17	685.21
H	645+11.90	0.50	685.16	685.19
I	645+21.90	0.50	685.13	685.13
☉ Brg. ☉ Pier 2	645+28.56	0.50	685.13	685.13
J	645+38.56	0.50	685.10	685.10
K	645+48.56	0.50	685.07	685.07
L	645+58.56	0.50	685.03	685.03
☉ Brg. E. Abut.	645+70.06	0.50	684.98	684.98
Back E. Abut.	645+71.90	0.50	684.97	684.97

BEAM 7

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+18.53	1.33	684.96	684.96
☉ Brg. W. Abut.	644+20.37	1.33	684.97	684.97
A	644+30.37	1.33	685.01	685.02
B	644+40.37	1.33	685.05	685.06
C	644+50.37	1.33	685.09	685.09
☉ Brg. ☉ Pier 1	644+61.87	1.33	685.12	685.12
D	644+71.87	1.33	685.14	685.16
E	644+81.87	1.33	685.15	685.18
F	644+91.87	1.33	685.16	685.20
G	645+01.87	1.33	685.15	685.19
H	645+11.87	1.33	685.15	685.18
I	645+21.87	1.33	685.13	685.14
☉ Brg. ☉ Pier 2	645+28.53	1.33	685.12	685.12
J	645+38.53	1.33	685.09	685.09
K	645+48.53	1.33	685.06	685.06
L	645+58.53	1.33	685.02	685.02
☉ Brg. E. Abut.	645+70.03	1.33	684.96	684.96
Back E. Abut.	645+71.87	1.33	684.95	684.95

DESIGNED	JMT
CHECKED	BLB
DRAWN	JMT
CHECKED	BLB

TOP OF SLAB ELEVATIONS - IV  
STRUCTURE NO. 022-0033

<b>rjngroup</b> Excellence through Ownership 200 West Front Street Wheaton, IL 60187	SHEET NO. 7	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	27 SHEETS	311	10HB-R	Du Page	53	23
			CONTRACT NO. 60B92			
		FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				