

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000					CODE NO	ITEM	UNIT		URBAN 1000				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	60	60					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	400	400				
25200110	SODDING, SALT TOLERANT	SO YD	60	60					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	160	160				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	120	120				
40600300	AGGREGATE (PRIME COAT)	TON	42	42					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	66	66				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	16	16					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	440	440				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	60	60					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	16	16				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1045	1045													
42001300	PROTECTIVE COAT	SO YD	82	82													
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	10327	10327													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	350	350													
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	300	300													
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	200	200													
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	150	150													
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3500	3500													
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	40	40													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7000	7000													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	60	60													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	400	400													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	350	350													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	40	40													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7000	7000													
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	60	60													