

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT		
20201006	GRADING AND SHAPING SHOULDERS	UNIT	170	170
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	70	70
25200110	SODDING, SALT TOLERANT	SQ YD	70	70
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	15	15
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	70	70
40600300	AGGREGATE (PRIME COAT)	TON	340	340
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	126	126
40600535	LEVELING BINDER (HAND METHOD), N70	TON	3	3
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,030	1,030
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SQ YD	1,100	1,100
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	280	280
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8,250	8,250
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	20	20
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	900	900
44000150	HOT-MIX ASPHALT SURFACE REMOVAL, 1/4"	SQ YD	13,800	13,800
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	21,900	21,900
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	6,500	6,500
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20	20
44000600	SIDEWALK REMOVAL	SQ FT	900	900
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400	400
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,620	1,620
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	240	240
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	1,140	1,140
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	960	960
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	2,160	2,160
44200990	CLASS B PATCHES, TYPE I, 12 INCH	SQ YD	10	10
44200994	CLASS B PATCHES, TYPE II, 12 INCH	SQ YD	230	230
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	150	150
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	250	250
44213200	SAW CUTS	FOOT	3,550	3,550
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	270	270
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,500	1,500
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	20	20
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	40	40
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	3

\* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT		
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3
63500105	DELINEATORS	EACH	18	18
63500110	DELINEATORS (SPECIAL)	EACH	17	17
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	440	440
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	67,300	67,300
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	1,600	1,600
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	15,200	15,200
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	4,400	4,400
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	140	140
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	38,500	38,500
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220	220
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28,900	28,900
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	800	800
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	7,600	7,600
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,200	2,200
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	4,750	4,750
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220	220
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	33,650	33,650
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	800	800
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	7,600	7,600
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	2,200	2,200
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	70	70
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	620	620
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	186	186
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,470	3,470
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1,800	1,800
X7010105	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
Z0017100	DOWEL BARS	EACH	800	800
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	75	75
Z0075300	TIE BARS	EACH	800	800

FILE NAME = N:\PROJ\3366\3366\_35\Design\ProposedPlan\3366\_35-03-Quantities.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alou	DESIGNED - NT	REVISED -
PLOT SCALE = 1/8000' / IN.	DRAWN - NT	REVISED -
PLOT DATE = 12/15/2009	CHECKED - WBL	REVISED -
	DATE - 12/11/2009	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**STONY ISLAND AVENUE  
ENTRANCE/EXIT RAMP OF I-94 TO US 1220 (95TH STREET)  
SUMMARY OF QUANTITIES**

F.A.P. RTE. 341	SECTION 42-2 (2 & 3) RS-3	COUNTY COOK	TOTAL SHEETS 23	SHEET NO. 3
SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 60107	
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				