

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | | SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|--|--------|-----------------------------------|------------------------|--|--|--|--|-----------------------|--|-------|-----------------------------------|------------------------|--|--|--|--|
| CODE NO | ITEM | UNIT | URBAN 100% STATE TOTAL QUANTITIES | 1000 | | | | | CODE NO | ITEM | UNIT | URBAN 100% STATE TOTAL QUANTITIES | | | | | |
| 44201791 | CLASS D PATCHES, TYPE II, 12 1/2 INCH | SO YD | 3879 | 3879 | | | | | 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 809 | 809 | | | | |
| 44201793 | CLASS D PATCHES, TYPE III, 12 1/2 INCH | SO YD | 3448 | 3448 | | | | | 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 1470 | 1470 | | | | |
| 44201796 | CLASS D PATCHES, TYPE IV, 12 1/2 INCH | SO YD | 1293 | 1293 | | | | | 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 6667 | 6667 | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SO YD | 235 | 235 | | | | | *78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 2023 | 2023 | | | | |
| 25200110 | SODDING, SALT TOLERANT | SO YD | 235 | 235 | | | | | *78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 40200 | 40200 | | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 118 | 118 | | | | | *78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 10100 | 10100 | | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 590 | 590 | | | | | *78000500 | THERMOPLASTIC PAVEMENT MARKING - LINE 8" | FOOT | 760 | 760 | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 220 | 220 | | | | | *78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 809 | 809 | | | | |
| 40600826 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 5820 | 5820 | | | | | *78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 1470 | 1470 | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | | | | | *78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 1680 | 1680 | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SO YD | 800 | 800 | | | | | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 1000 | 1000 | | | | |
| 40603595 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 | TON | 14490 | 14490 | | | | | *88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 6200 | 6200 | | | | |
| 42001300 | PROTECTIVE COAT | SO YD | 450 | 450 | | | | | X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 51.4 | 51.4 | | | | |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SO YD | 135822 | 135822 | | | | | Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 62 | 62 | | | | |
| 44000198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SO YD | 2500 | 2500 | | | | | | | | | | | | | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 1600 | 1600 | | | | | | | | | | | | | |
| 44003510 | MEDIAN REMOVAL PARTIAL DEPTH | SQ FT | 15,387 | 15,387 | | | | | | | | | | | | | |
| 55039700 | STORM SEWERS TO BE CLEANED | FOOT | 4080 | 4080 | | | | | | | | | | | | | |
| 60300310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 40 | 40 | | | | | | | | | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 | | | | | | | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | | | | | | | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | | | | | | | | | | |
| 70102632 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602 | L SUM | 1 | 1 | | | | | | | | | | | | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | | | | | | | | | | | | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 20000 | 20000 | | | | | | | | | | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SO FT | 2023 | 2023 | | | | | | | | | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 40200 | 40200 | | | | | | | | | | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 10100 | 10100 | | | | | | | | | | | | | |
| 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 760 | 760 | | | | | | | | | | | | | |

* SPECIALTY ITEMS