



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME = 4085.852-TR1.dwg	USER NAME = GHA	DESIGNED - JRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY INFORMATION SIGNING			FAU. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		DRAWN - ZCW	REVISED -		SCALE N.A.	SHEET NO. OF	SHEETS	STA.	TO STA.	VARIES	2009-105-TS	KANE	36	35
		PLOT SCALE = 1" = .0833'	CHECKED - KLB		REVISED -									
		PLOT DATE = 12/9/2009	DATE - 11/20/09		REVISED -									
												CONTRACT # 60J01		
												ILLINOIS FED. AID PROJECT		