

CODE NO.	ITEM DESCRIPTION	SP PROV	UNIT	TOTAL QUANTITY	FEDERAL QUANTITY (80%)	LOCAL QUANTITY (20%)	LOCAL QUANTITY (100%)
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		UNIT	58	46.4	11.6	0
20101000	TEMPORARY FENCE		FOOT	600	480.0	120.0	0
20101100	TREE TRUNK PROTECTION		EACH	6	4.8	1.2	0
△ 20101200	TREE ROOT PRUNING		EACH	8	6.4	1.6	0
△ 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)		EACH	3	2.4	0.6	0
△ 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)		EACH	5	4.0	1.0	0
△ 20101700	SUPPLEMENTAL WATERING		UNIT	10	8.0	2.0	0
20200100	EARTH EXCAVATION		CU YD	554	443.2	110.8	0
20400800	FURNISHED EXCAVATION		CU YD	700	560.0	140.0	0
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION		SQ YD	4,829	3863.2	965.8	0
△ 21101615	TOPSOIL FURNISH AND PLACE, 4"		SQ YD	4,742	3793.6	948.4	0
△ 25000100	SEEDING, CLASS 1		ACRE	0.98	0.8	0.2	0
△ 25000400	NITROGEN FERTILIZER NUTRIENT		POUND	74	59.4	14.9	0
△ 25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	74	59.4	14.9	0
△ 25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	74	59.4	14.9	0
△ 25100630	EROSION CONTROL BLANKET		SQ YD	4,723	3778.4	944.6	0
35101800	AGGREGATE BASE COURSE, TYPE B 6"		SQ YD	4,928	3942.6	985.6	0
40300200	BITUMINOUS MATERIALS (PRIME COAT)		TON	6.1	4.9	1.2	0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50		TON	708.0	566.4	141.6	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH		SQ FT	1,395	1116.0	279.0	0
42400800	DETECTABLE WARNINGS		SQ FT	430	344.0	86.0	0
44000500	COMBINATION CURB AND GUTTER REMOVAL		FOOT	124	99.2	24.8	0
60255500	MANHOLES TO BE ADJUSTED		EACH	5	4.0	1.0	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12		FOOT	275	220.0	55.0	0
67100100	MOBILIZATION	*	L SUM	1	0.8	0.2	0
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	*	L SUM	1	0.8	0.2	0
△ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	280	224.0	56.0	0
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"		FOOT	6,899	5519.2	1379.8	0
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"		FOOT	1,434	1147.2	286.8	0
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"		FOOT	278	222.4	55.6	0
78300100	PAVEMENT MARKING REMOVAL		SQ FT	275	220.0	55.0	0
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"		FOOT	55	44.0	11.0	0
△ A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED		EACH	3	2.4	0.6	0
△ B2001666	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED		EACH	3	2.4	0.6	0
△ K0036120	MULCH PLACEMENT 4"	*	SQ YD	93	74.4	18.6	0
X0321309	CONCRETE PAD	*	SQ YD	7	5.6	1.4	0
△ X0322453	WEED CONTROL, PRE-EMERGENT	*	POUND	5	4.0	1.0	0
X0323973	SEDIMENT CONTROL, SILT FENCE	*	FOOT	100	80.0	20.0	0
H000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABE DEPTH	*	SQ YD	2402	1921.6	480.4	0
X0444100	BENCHES	*	EACH	1	0.0	0.0	1
XX006653	FENCE (SPECIAL)	*	FOOT	121	96.8	24.2	0
Z0064800	SELECTIVE CLEARING	*	UNIT	1	0.8	0.2	0

△ SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		CHICAGO PARK DISTRICT - JACKSON PARK MARQUETTE DRIVE BICYCLE PATH

SCALE: 1" = 20'
DATE: 10/16/2009
DRAWN BY: MJP
CHECKED BY: TB